

AYLWARD PROD. CO.
McAllister No. 1

SEC. 9 T. 12 R. 13W.
NE SE

County Russell.

Total Depth. 3568
Comm. 8-30-36 Comp. 11-2-36
Shot or Treated.
Contractor. The Aylward Prod. Co.
Issued. 12-12-36

CASING.

DEC 12 1936

12 1/2" 512' 53/16" 3335' UR 3432'
10" 815'
8 1/4" 2430' UR 2465'
65/8" 2985'

Plotted Texas Co.



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

cellar	12	shale grey	1945	lime broken	3115
post rock	17	lime	1960	lime	3160
mud yellow	40	slate	1965	lime sdy	3165
shale blk	90	lime	1980	lime	3235
shale blue	155	slate	1990	slate	3242
sand	185	lime	2000	lime	3265
mud blue	190	red rock	2005	shale blue	3275
sand	200	lime	2055	lime	3295
5 BWPFR 190-95		red rock	2070	shale	3300
shale grey	210	lime	2135	lime	3305
mud yellow	240	red rock	2145	shale	3315
slate	260	lime	2180	lime broken	3325
water sand	270	shale grey	2185	conglomerate	3330
7 BWPFR 260-70		lime	2220	lime	3358
red rock	285	slate	2225	shale brown	3365
slate	315	lime	2230	lime	3370
red rock	350	slate	2250	conglomerate	3388
sand	360	lime	2260	lime	3405
HFW 350-60		shale sdy	2275	sand	3415
shale blue	403	lime	2280	2 BWPFR 3405-10	
sand hard	405	shale grey	2305	HFW 3410-15'	
slate	425	slate	2335	sand & red rock	3420
shale blue	495	shale blue	2385	lime	3425
slate	510	slate	2420	conglomerate	3435
red rock	811	lime	2435	shale light	3450
anhydrite lime	815	5 BWPFR 2423-28		conglomerate	3475
5 BWPFR 650-65		slate	2460	slate light	3490
lime	845	lime	2490	shale light	3505
slate blue	850	shale	2500	slate light	3550
red rock	875	lime	2505	lime	3560
shale blue	880	shale blue	2510	lime sdy	3568
red rock	970	lime	2515		
slate gyp shells	1025	shale grey	2520	Total Depth.	
red rock	1040	slate	2525	HFW 3567-68	
shale blue	1150	lime	2545		
gyp shells	1170	shale grey	2550		
salt	1430	lime	2610		
lime	1470	slate	2620		
lime broken	1480	lime	2635		
lime	1560	slate	2660		
shale grey	1570	lime	2675		
red rock	1575	slate	2690		
lime	1615	lime	2715		
slate	1625	slate	2725		
red rock	1635	lime	2765		
lime	1645	slate	2770		
lime broken	1655	lime	2960		
lime	1675	1/2 BWPFR 2780 2 BWPFR 2840-45			
lime broken	1685	slate	2980		
lime	1745	shale brown	2985		
shale green	1750	lime	2992		
shale blue	1760	red rock	3005		
lime	1850	slate	3015		
red rock	1860	lime	3030		
lime	1885	lime broken	3045		
shale	1890	lime	3105		
lime	1935	slate	3110		