

JOHN O. FARMER, INC.

P.O. Box 352

Russell, KS 67665

(785) 483-3144

Distribution:

Presley Petroleum

Terry Marple

Gerald Furseth Revocable Trust

W.C. Talbott

Robert Schmidt

Grand Prairie Inc.

Nancy Talbott

Pinnacle Resources

Aven Weaverling

TAYLOR A #1

(SE Mellard 3-D)

840' FNL & 1690' FWL

Sec. 20-12S-14W

Russell County, Kansas

1616 'G.L.

1624 'K.B.

Drilling Contractor:

Discovery Drilling - Rig #2

Cell. 785-635-1412

Toolpusher - Dave DreilingGeologist - Rod Trembley

Cell 402-560-0715

Office 402-434-6075

API #15-167-23304-0000

TIGHT HOLE - DO NOT RELEASE INFORMATION

10/13/2005

MIRU, spud.

10/14/2005

440', drilling; plan to set surface @ 518'.

10/15/2005

1037', drilling

10/16/2005

2152', drilling

10/17/2005

2825', running DST #1

DST #1 2794'-2825' (Lansing A&B)

30" - 30" - 60" - 60"

IF: Surface build to 2", no blow back

FF: Surface build to 1 1/2", no blow back

REC: 57' Muddy Water (70% W, 30% M)- CI 27,000 ppm

20' Drilling Mud

77' Total Fluid

FP: 14-33#, 34-52#

SIP: 329-334#

HP: 1350-1338#

BHT: 95 degrees

DST #2 2826'-2843' (Lansing C)

30" - 30" - 30" - 30"

IF: Surface blow died in 13", no blow back

FF: No Blow, no blow back

REC: 20' Watery Mud (16% W, 84% M)

FP: 14-17#, 18-21#

SIP: 350-336#

HP: 1354-1350#

BHT: 92 degrees

10/18/2005

2985', drilling

Plugged well as follows: 1st Plug @ 3050' w/25 sx, 2nd plug at 700' w/25 sx, 3rd plug @ 350' w/ 50sx, 4th plug @ 40' w/10 sx. 10 sx in mousehole, 15 sx in rathole. 135 sx total, 60/40 Poz, 6% Gel by Allied. Completed @ 4:45 am, released rig. State Contact: Bruce Bayse

Rains & Williamson			Estim. from 3D Seismic	JOHN O. FARMER, INC.			
Steckel A #1				TAYLOR A #1			
N/2 S/2 SE Sec. 18-12S-14W				1624			
1619 KB				Sample		E-Log	
Anhydrite	680	939		689	935	690	934
Topeka	2510	-891	-875	2521	-897	2522	-898
Heebner	2729	-1110	-1100	2741	-1117	2742	-1118
Toronto	2752	-1133		2761	-1137	2761	-1137
Lansing	2783	-1164		2791	-1167	2792	-1168
B/KC	3041	-1422		3052	-1428	3052	-1428
Arbuckle	3082	-1463		3086	-1462	3086	-1462
RTD	3102	-1483		3150	-1526		
LTD						3151	-1527