

Operator

RAINS & WILLIAMSON OIL Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDOW, ETC.:

D&A

Well No.

1

Lease Name

WEILERT

S 6 T 12 R 14 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST# 1, 2959-3005 30 (45) 60 (60) strong blow rec. 560' slightly gas 7 oil cut muddy salt water, IFP 53#-106#, FFP 159#-245#, ISIP 690#, FSIP 669#.			ANHYDRITE	842 (+932)
			B/ANHYDRITE	880 (+894)
			TOPEKA	2645 (-871)
			HEEBNER	2899 (-1125)
			TORONTO	2920 (-1146)
			LANSING	2954 (-1180)
DST # 2, 3018-48, 30 (45) 30 (30), weak blow first opening, no blow second opening, rec. 25' drilling mud, IFP 53#-31#, FFP 53#-21#, ISIP 480#, FSIP 85#.			BASE KANSAS CITY	3220 (-1446)
			CONGLOMERATE	3250 (-1476)
			LOG TOTAL DEPTH	3312 (-1538)
DST # 3, 3106-3130, 30 (30) 30 (30) weak blow, rec. 60' slightly oil & water cut mud, IFP 53# 31#, FFP 63#-53#, ISIP 794#, FSIP 773#.				
DST # 4, 3130-3155, 30 (30) 30 (30) very weak blow 1st opening, no blow 2nd opening, rec. 10' watery mud with specks oil, IFP 96#-64#, FFP 86#-63#, ISIP 985#, FSIP 963#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received


 Signature

WILSON RAINS PRESIDENT

Title

6/30/80

Date