

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas

7-12-14W

Company - SOHIO AND APPLEMAN ETAL
Farm - Roda No. 1SEC. 7 T. 12 S. 14W
CE/2 SE NETotal Depth. 3280
Comm. 3-3-50 Comp. 3-15-50
Shot or Treated.
Contractor.
Issued. 4-15-50County. Russell
KANSASCASING:
8" 147'Elevation. 1755(m)
1757 R.B. (end)

Production. Dry

Figures Indicate Bottom of Formations.

surface clay, rock	45
shale blk, rock	120
shale blue, rock	146
shale, shells	290
sand	360
shells, shale, iron	
strks	430 ✓
iron strks	490 ✓
shale gry	500
sand	515
shale gry	530
red bed	545
shale, redbed, iron	590 ✓
red bed	619
anhyd.	860
redbed, shells	1120
shale, anhyd. strks	1280
shale, shells	1440
anhydrite, shells	1445
salt strks	1465
anhyd. shells	1610
shale, shells	1725
lime shells, shale	1790
lime	1820
lime, shale	1835
lime hrd	1885
lime	2095
lime, shale	2270
shale, red rock	2470
lime, shale	2621
lime	3280
Total depth	

Shows of Oil, gas and Water.

DST 2944-85. 50" 10' OCM. and 50' MSalt wtr.

BHP 560 #. DST 3008-22. 50" 34' muddy salt wtr.

BHP 520 #.

Tops:	
Anhydrite	819
Topeka	2621
Heebner	2874
Dodge	2899
Lansing	2927
Arbuckle	3259