

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.)

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Rains & Williamson Oil Co., Inc.

API NO. 15-167-21,873

ADDRESS 435 Page Court, 220 W. Douglas

COUNTY Russell

Wichita, Kansas 67202

FIELD _____

**CONTACT PERSON Juanita Green

PROD. FORMATION _____

PHONE 265-9686

LEASE Roda "A"

PURCHASER _____

WELL NO. #1

ADDRESS _____

WELL LOCATION SW SW SE

DRILLING Rains & Williamson Oil Co., Inc.

_____ Ft. from _____ Line and

CONTRACTOR _____

_____ Ft. from _____ Line of

ADDRESS 435 Page Court, 220 W. Douglas

the SEC. 7 TWP. 12S RGE. 14W

Wichita, Kansas 67202

WELL PLAT

PLUGGING Same

CONTRACTOR _____

ADDRESS _____

KCC _____
KGS
(Office Use)

RECEIVED
STATE CORPORATION COMMISSION

TOTAL DEPTH 3195' PBDT APR 19 1982

SPUD DATE 2-22-82 DATE COMPLETED APR 28 1982

ELEV: GR 1705 DF _____ KB 1710

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 780' DV Tool Used? _____

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I, _____

Wilson Rains OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) Rains & Williamson Oil Co., Inc.

OPERATOR OF THE Roda "A" LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 2 DAY OF March, 19 82, AND THAT

92417

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2875-2920, 30 (30) 30 (30). Rec. 60' WM. No flow pressures. IBHP 506, FBHP 459.			<u>E. LOG TOPS</u>	7-12-14w
DST #2 - 2951-2974, 30 (30) 60 (30). Rec. 220' MW, S.O. top tool. FP's 55-99, 110-154. IBHP 407, FBHP 396.			Anhydrite	782 (+928)
			Topeka	2563 (-853)
			Heebner	2817 (-1107)
			Lansing	2870 (-1160)
			BKC	3130 (-1420)
			Arbuckle	3180 (-1470)
			LTD	3198 (-1488)
DST #3 - 3000-3040, 30 (30) 60 (30). Rec. 720' SW. FP's 77-220, 253-363. IBHP 407, FBHP 407.				

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	780'	Class A	400 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

P1

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 7 T. 12S R. 14W

LOC. SW SW SE

WELL NAME: Roda "A" #1

COUNTY: Russell

RIG NO. #9

TOTAL DEPTH 3195'

ELEVATION 1705' GL 1710' KE

COMMENCED: 2-22-82

COMPLETED: 3-2-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 780' w/400 sx. Class A, 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	1216
Shale & Lime	2230
Lime & Shale	2670
Shale & Lime	2920
Lime	2974
Shale & Lime	3040
Lime & Shale	3110
Lime	3195
<u>ROTARY TOTAL DEPTH</u>	<u>3195</u>

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1982
CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas)
COUNTY OF Sedgwick)

SS:

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1982