

TYPE State Geological Survey AFFIDAVIT OF COMPLETION FORM

SIDE ONE WICHITA BRANCH

7-12-1400  
 REC-1 WELL HISTORY  
 Date: MAR 1 1984  
 FROM CONFIDENTIAL

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5146 EXPIRATION DATE \_\_\_\_\_

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-167-22,066

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Russell

Wichita, Kansas 67202 FIELD \_\_\_\_\_

\*\* CONTACT PERSON Juanita Green PROD. FORMATION \_\_\_\_\_

PHONE 265-9686

PURCHASER \_\_\_\_\_ LEASE Roda "A"

ADDRESS \_\_\_\_\_ WELL NO. #2

WELL LOCATION SW NW SE

DRILLING Rains & Williamson Oil Co., Inc. 1650 Ft. from South Line and

CONTRACTOR 435 Page Court, 220 W. Douglas 2310 Ft. from East Line of

ADDRESS Wichita, Kansas 67202 the (Qtr.) SEC 7 TWP 12S RGE 14 (W).

PLUGGING Same WELL PLAT \_\_\_\_\_ (Office Use Only)

CONTRACTOR \_\_\_\_\_

ADDRESS \_\_\_\_\_

TOTAL DEPTH 3225' PBTD \_\_\_\_\_

SPUD DATE 2-18-83 DATE COMPLETED 2-25-83

ELEV: GR 1715 DF \_\_\_\_\_ KB 1720

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE \_\_\_\_\_

Amount of surface pipe set and cemented 793' DV Tool Used? \_\_\_\_\_

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry Disposal, Injection, Temporarily Abandoned, OWWO. Other \_\_\_\_\_

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

# A F F I D A V I T

Wilson Rains, President, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.


KCC \_\_\_\_\_  
 KGS ☒  
 SWD/REP \_\_\_\_\_  
 PLG. \_\_\_\_\_

SIDE TWO

92418

ACO-1 WELL HISTORY XX,

OPERATOR Rains &amp; Williamson Oil Co., Inc. LEASE, Roda "A" #2 SEC. 7 TWP. 12S RGE. 14 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO.

Show all important zones of porosity and contents thereof; corad intervals, and all drill-stem tests, including depth interval tests, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
DST #1 - 2894-2936, 30 (30) 60 (30). Rec. 15' O&GCM, 120' V S1.0&GCM, 60' GCM w/spots oil. FP's 55-66, 88-111. IBHP 411, FBHP 400.			E. LOG TOPS	
			Anhydrite	782 (+938)
			Topeka	2578 (-858)
			Heebner	2834 (-1114)
			Lansing	2886 (-1166)
			Arbuckle	3202 (-1482)
			LTD	3223 (-1503)
DST #2 - 2950-2990, 30 (30) 30 (30). Rec. 35' G&O spotted mud, 90' oil specked WM. FP's 44-44, 77-88. IBHP 355, FBHP 355.				
DST #3 - 3044-3061, 30 (30) 30 (30). Rec. 50' GCWM w/spots oil, 300' GCMW w/spots oil. FP's 66-88, 177-200. IBHP 377, FBHP 377.				
If additional space is needed use Page 2, Side 2				

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23#	793'	60/40 poz.	375 sx.	2% gel, 3% cc.

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

81

DRILLER'S LOG (C)(L)

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 7 T. 12S R. 14W

LOC. SW NW SE

WELL NAME: Roda "A" #2

COUNTY: Russell

RIG NO. #9

TOTAL DEPTH 3225'

ELEVATION 1715 GL 1720 KB

COMMENCED: 2-18-83

COMPLETED: 2-25-83

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 793' w/375 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand	60
Sand & Clay	110
Redbed & Shale	530
Shale & Redbed	1240
Shale & Lime	1805
Lime & Shale	2860
Lime	3225
ROTARY TOTAL DEPTH	<u>3225</u>

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

of Rains & Williamson Oil Co., Inc.