



## SIDE TWO

Operator Name Rains &amp; Williamson Oil Co. Lease Name Becker "C" Well# ...1 SEC. 15... TWP. 12S... RGE. .... 14

## WELL LOG

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

## Drill Stem Tests Taken

☐ Yes ☐ No

## Samples Sent to Geological Survey

☐ Yes ☐ No

## Cores Taken

☐ Yes ☐ No

## Formation Description

☒ Log ☐ Sample

## Name

## Top

## Bottom

DST #1 - 2957-2990, 30 (30) 30 (30).  
Rec. 5' mud. FP's 30-30, 40-40.  
IBHP 194, FBHP 194.

DST #2 - 2991-3008, 30 (30) 30 (30).  
Rec. 5' mud. FP's 32-32, 53-53.  
IBHP 825, FBHP 761.

DST #3 - 3115-3195, 30 (30) 30 (30).  
Rec. 65' mud w/spots oil. FP's 43-43,  
64-64. IBHP 1037, FBHP 995.

|             |              |  |
|-------------|--------------|--|
| Anhydrite   | 811 (+949)   |  |
| B/Anhydrite | 845 (+9)     |  |
| Topeka      | 2636 (-876)  |  |
| Heebner     | 2899 (-1139) |  |
| Lansing     | 2951 (-1191) |  |
| BKC         | 3220 (-1460) |  |
| Arbuckle    | 3320 (-1)    |  |
| LTD         | 3363 (-1603) |  |

## CASING RECORD

☒ new☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

| Purpose of string | size hole drilled | size casing set (in O.D.) | weight lbs/ft. | setting depth | type of cement | # sacks used | type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|----------------|--------------|----------------------------|
| ...Surface.....   | ..12 1/4".....    | 8.5/8"                    | ..23#...       | ...301'.....  | Sunset         | 175 sx.      |                            |
| .....             | .....             | .....                     | .....          | .....         | .....          | .....        | .....                      |
| .....             | .....             | .....                     | .....          | .....         | .....          | .....        | .....                      |
| .....             | .....             | .....                     | .....          | .....         | .....          | .....        | .....                      |

## PERFORATION RECORD

shots per foot

specify footage of each interval perforated

## Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

p1

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 15 T. 12S R. 14W

LOC. NE SE SE

WELL NAME: Becker "C" #1

COUNTY: Russell

RIG NO. #9

TOTAL DEPTH 3368'

ELEVATION 1755 GL 1760 KB

COMMENCED: 11-24-84

COMPLETED: 12-1-84

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 301' w/175 sx. Sunset.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

|                           |             |
|---------------------------|-------------|
| Clay & Sand               | 304         |
| Shale & Sand              | 490         |
| Sand, Shale & Redbed      | 809         |
| Shale & Shells            | 1585        |
| Shale & Lime              | 2665        |
| Lime & Shale              | 2980        |
| Lime                      | 3008        |
| Lime & Shale              | 3195        |
| Lime                      | 3368        |
| <u>ROTARY TOTAL DEPTH</u> | <u>3368</u> |

JAN 16 1985

State Geological Survey

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

RECEIVED  
STATE CORPORATION COMMISSION

JAN 07 1985