


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

GOUGH DAVIS
Mary H. Funk No. 1.

26-12-1403
SEC. 26 T. 12 R. 14 W
NW NE NW

Total Depth. 3393'
Comm. 8-27-43 Comp. 10-6-43
Shot or Treated.
Contractor. Stearns Drlg.Co.
Issued. 10-30-43

County. Russell



CASING:

15 1/2" 318'6" 8" 2410'
12 1/2" 546' 7" 2962'1"
10" 816' 5 3/16" 3224'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	15	lime	2100	lime	3214-3233
sand	25	shale blue	2115	ran 3224' of 5 3/16" csg	
shale blue	175	lime	2135	shale blue	3237
shale brown	200	shale & shells	2150	lime	3246
shale gy	225	shale	2155	shale- red rock	3250
shale blue	250	lime hd	2180	lime	3267
sand HFW 250-70	270	lime	2200	shale blue	3271
shale blue	290	shale blue	2215	lime	3277
redrock	295	lime	2235	conglomerate	3290
shale blue	310	shale blue	2250	Simpson	3300
shale red	325	lime	2256	?	3300-3336
shale blue	340	shale blue	2270	lime Arbuckle	3393
sand HFW 340-50	350	lime	2280	Total Depth.	
shale blue	355	shale blue	2285		
shale red	370	lime	2292		
shale blue	400	shale & shells	2310	2 BWPB 3346-52	
sand	415	lime	2340	wtr 3387-93	
shale blue	490	shale blue	2405		
shale gy	500	lime	2409		
shale blue	512	ran 2410' 8" casing			
shale red	522	SIM 2409 equals 2416			
red rock(2BWPB 670-75)	815	lime	2416- 2430		
anhydrite(wtr 720-30)	820	shale blue	2475		
lime	850	lime	2480		
shale red	855	lime -caving	2520		
red rock	975	lime	2525		
shale gy	1020	shale blue	2530		
shale red	1055	lime	2548		
red rock	1060	shale sdy	2610		
shale blue	1075	shale blue	2615		
shale gy	1090	lime	2620		
shale brown	1103	shale blue	2623		
shale gy	1125	lime	2638		
salt	1135	shale blue	2643		
salt brkn	1160	lime	2655		
salt	1435	lime-caving	2667		
shale blue	1450	shale blue-caving	2677		
salt brkn	1465	lime sft	2687		
shale blue	1470	ran 2685' 7" casing			
lime brkn	1500	shale blue	2705		
lime	1510	lime	2775		
shale blue	1515	shale blk	2780		
lime	1530	lime	2917		
shale blue	1540	shale blue	2927		
shale & shells	1555	lime	2943		
lime	1577	lime Dodge	2946		
red rock	1600	shale blue	2950		
lime	1628	shale red	2955		
shale blue	1633	shale	2960		
shale red	1640	lime K. C.	2980		
shale green	1645	Underreamed & set			
lime	1740	7" csg to 2962			
shale blue	1745	shale blue	2989		
lime	1830	lime	3032		
shale blue	1840	shale	3036		
red rock	1850	lime	3173		
lime	1908	shale blk	3175		
shale blue	1922	shale green	3179		
lime	2022	lime	3200		
shale red	2042	shale	3206		