

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

8-12-15W

Company - H. F. WILCOX OIL & GAS CO.
Farm - OSWALD VALERIUS No. 11


SEC. 8 T. 12 R15W
NW NW NE

DEEPENING RECORD

Total Depth. 3234
Comm. 11-4-25
Shot or Treated.
Contractor.
Issued. 9-16-50

Comp. 1-18-36

County. Russell
KANSAS



CASING:
20" 9' 7"
15 1/2" 480' P.
12 1/2" 868' P.
10" 1495' P.

8 1/4" 2415' P.
6 5/8" 2640'
5 3/16" 2935'

Elevation. 1825
(1824.9')

Production. 1st 24 hrs. 96 bbls.

Figures Indicate Bottom of Formations.

yellow	15	shale brown	2030
blue	50	lime gy	2050
slate blue	120	shale brown	2065
slate blue	150	redrock	2100
slate wh	195	slate blue	2110
slate brown	210	lime gy sdy	2140
redrock	245	shale brown	2160
sand br, HFV 255	258	shale broken	2230
shale brown	280	shale brown	2235
redrock	318	lime wh	2260
sand gy	336	slate blue	2282
slate blue	345	lime gy	2294
sand gy	408	slate blue	2364
iron	410	shale brown sdy	2378
sand	418	slate blue	2395
slate wh	435	shale sdy	2405
sand gy	455	slate blue	2418
slate wh	475	lime wh	2438
sand & iron	480	shale brown	2446
shale blue	505	lime gy	2460
sand wh	520	shale brown	2472
slate red	535	lime	2500
shale sdy	555	slate blue	2535
redrock	868	good show oil 2460'	
lime gy	910	lime	2550
redrock	1010	lime gy	2572
lime	1015	shale brown	2595
slate blue	1050	shale sdy	2605
redrock	1135	shale blue	2629
lime	1140	lime gy	2661
slate blue	1220	slate blue	2665
slate & salt broken	1240	sand	2670
salt	1465	show oil 2665-70'	
shale blue	1495	lime gy	2700
lime wh	1498	lime sdy	2705
slate blue	1530	slate blue	2710
lime	1535	lime wh	2720
slate	1580	slate blue	2725
slate blue	1598	lime gy	2750
redrock	1620	slate blue	2755
lime wh	1628	SIM 2750'	
slate blue	1660	lime gy	2796
lime gy	1665	lime gy	2805
redrock soft	1675	lime wh	2825
lime	1690	lime gy	2857
shale blue	1705	sand gy	2870
redrock	1738	lime sdy	2880
lime gy	1752	slate blk	2884
slate blue	1820	lime wh	2911
lime wh	1850	show oil 2910	
slate blue	1859	slate blue	2917
lime wh	1868	lime shell wh	2918
redrock	1905	redrock	2926
lime wh	1910	slate green	2 935
slate blue	1955	SIM 2935	
shale brown	1978	lime sdy top pay	2939
lime wh	1986	lime wh	2949 1/2

lime soft brown	2950
shale blue	2952
lime, shell	2953
shale blue	2958
lime gy	2961
lime brown oil	2963
Pay 2961-62'	
lime gy	2964
Total depth	

DEEPENING RECORD

Company Sohio Petro.
Comm. 10-22-47
Comp. 11-19-47
Prod. 54 bbbbls. oil per
day plus tr. wtr.
OTD 2964

Arbuckle 3234
Total depth
Tops:
Lansing 2935
Arbuckle 3230

Remarks:
1 BOPH & NW
1000 acid
340' 4 1/2" liner @
3200', dp & DD 3234 TD