

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508E. Murdock, Wichita, Kansas

8-12-15W


Company - SOHIO PETROLEUM CO.
Farm - Ed Oswald "A" No. 9

SEC. 8 T. 12 R. 15W
SW NE SW

DEEPENING RECORD

Total Depth. 3239
Comm. 10-8-46 Comp. 10-26-46
Shot or Treated.
Contractor.
Issued. 10-28-50

County. Russell
KANSAS



CASING:

10" 650'
5" 3228½'

Elevation. 1844 ~~220~~

Production. Est. 200 bbls. oil

Figures indicate Bottom of Formations.

surface clay	50	SHOWS OF OIL, GAS & WTR: DP & DD 3236 TD, S 2 BOPH; 1000 A; S 8 BOPH; 2500 A; S 9 BOPH-5 hrs.
sand	75	
sand, shale	260	Pumping on pump:
lime, shale	620	Spotted por & staining 2840-50;
shale, shells	660	SO 2863-70; 2940-46; 2985-92;
redbed, shale	800	3011-17; and 3026-38.
redbed, pyrite	870	Oolitic por & good sat.
redbed	875	
anhyd.	910	
shale, shells	1255	
sand, shale	1530	
lime, shale	1620	
lime	1650	
lime, shale	1870	
lime	2045	
lime, shale	2242	
lime brkn, shale	2305	
lime, shale	2842	
lime	2864	
lime, shale	2927	
lime	2967	
lime, shale	2998	
lime	3110	
cong.	3120	
lime, shale	3236	
Total depth		

Tops:
Lansing 2934
Arbuckle 3228

DEEPENING RECORD

Comm: 10-2-46
Comp: 11-13-46
Prod: Pump 9 bbls oil.
Casing: 5½" 3228'
Old total depth 3236
lime 3239
Total depth

Tops:
Arbuckle 3236