

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. NEc SE NW DEEPENING RECORD. Sec. 8 T..12 R. 15W.

Casing Record.

10" 2057'11" Farm. Oswald

County. Russell.

No. 9

20"10'6 84"2635 Company. Mid West Exploration Co.


153"376'265/8"2918'4" Contr.

123"38'1053/16" Comm. 1-23-25

Comp. 1-16-26

Total Depth. 3235 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To:



Elevation.

Figures Indicate Bottom of Formations.

Date Issued. 11-24-34

Initial Production.

188 B. 1st 24 Hr. on pump TD 2966

New Prod. 20 bbls T.D. 3016.

Formation	Depth.
shale	30
shale blue	200
red rock	235
water sand	240
red rock	310
sand	360
shale	380
sand	395
lime	410
sand	445
shale	455
shale blk	485
sand white	505
shale	520
sand	540
red rock	845
lime	885
red rock	1010
shale blue	1045
red rock	1090
shale blk	1150
salt	1490
slate	1515
lime	1525
slate	1535
lime	1545
slate	1550
lime	1570
red rock	1595
lime	1625
red rock	1635
broken lime	1645
lime hard	1655
red rock	1695
lime	1730
broken lime	1785
lime	1815
broken lime	1875
lime	1900
red rock	1920
lime	2015
red rock	2050
lime	2110
red rock	2125
slate	2155
lime	2165
lime broken	2185
lime	2195
lime broken	2230
shale	2260
lime	2270
slate	2290
lime	2300
slate	2350

Formation	Depth.
shale blue	2385
lime	2405
slate	2445
lime	2455
slate	2495
lime	2505
shale blue	2525
lime	2530
slate	2540
sdv lime	2580
lime	2595
slate	2600
lime	2620
shale	2630
lime show blk oil	2635
lime	2640
broken lime	2700
lime light	2840
sdv lime	2850
lime soft	2865
lime	2880
slate	2885
lime	2895
shale blue	2920
Oswald	2930
lime	2935
slate	2942
lime	2955
slate	2960
lime	2966
TD.	

DEEPENING RECORD.

Old T.D. 2966

Comm. 5-27-30 Comp. 6-26-30

Prod. 20 bbls.

lime	2966-	2969
shale blue		2978
lime		2988
lime oil		3007
lime shells		3010
lime sdv oil		3016 TD.

OVER

Stanolind Oil and Gas Co.
Ed. Oswald No. 24.
8-12-15W.

DEEPENING RECORD.

Old T.D. 3016

Comm. '9-18-34 Comp. 10-8-34
Prod. 188 B. 2nd 24 hours.

Cable tools 3025 to 3235
lime 3033
lime grey 3055
lime grey hard 3060
lime white ha rd. 3065
lime grey 3083
shale red soft 3085
lime grey hard 3102
lime shells and shale red 3110
lime grey ha rd 3113
slate blk 3115
lime grey 3187
red rock 3211
sand 3235
Total Depth.

1st pay 3213-3220
more oil 3220-3235

2 5/8 casing 2920.

Lansing Oswald 2920-3127
Gorham sand 3211-3235,

1st 15 hours 72 bbls.,
2nd 24 hours 188 bbls.,