

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDGWICHITA, KANSAS

72-950  
 Sec. 8 T. 12 R. 15W  
 DEC 17 1932

Location. SE SW NW DEEPENING RECORD.

330' fr S 330' fr W of Center line of NW<sup>1</sup>/<sub>4</sub>

**Casing Record.**

10" 2412 Farm. Ed. Oswald No. 83 2 (DRL)  
 20" 21 8" 2647 Company. Mid West Refining Co. (2167)  
 18<sup>1</sup>/<sub>2</sub>" 395 65/8" 2925' 6 Contr.  
 12<sup>1</sup>/<sub>2</sub>" 877 53/16" Comm. 4-20-25 Comp. 6-21-25  
 Total Depth. 3217 Shot Quarts Between.  
 Correspondence Regarding This Well Should Be Referred To.

County, Russell.



Elevation. 1848.2

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 12-17-32

150 B. TD. 2959

Swabbed 120 B per day TD. 3102

New Prod- Swabbed 83 bbls per day TD 3217

Formation	Depth	Formation	Depth	Formation	Depth.
slate blue	160	shale blue	1895	broken lime & red rock	3116
slate grey	210	lime	1925	sdv lime oil & gas	3122
slate red	240	shale red	1930	sdv lime	3125
slate grey	255	shale red	1940	shale	3127
sand and water	265	lime	1970	sdv lime	3134
slate red	300	shale red	2005	shale blue	3142
shale red	320	lime	2010	sdv lime	3148
shale lime	325	shale red	2050	sdv lime Oil	3153
sand	350	lime water	2070	shale blue	3166
sdv shale	408	shale red	2090	lime	3179
shale blue	425	lime	2105	shale blue	3186
sand water	450	shale red	2160	lime brown	3196
lime	455	lime	2180	broken lime & shale	3201
sand	472	shale grey	2235	lime	3211
iron	475	shale grey	2288	sand red	3217
iron and lime	480	shale grey	2325	TD.	
iron	485	lime wtr	2365		
shale blk	490	shale blue	2385		
sdv shale blue	535	shale blk	2412		
sdv shale red	540	lime	2428		
shale light	545	shale blue	2440		
sdv shale light	565	sand gas 4 M.	2445		
sdv shale red	580	shale blue	2450		
lime	585	shale blue	2495		
mud red	595	lime	2500		
sdv shale red	605	shale blue	2505		
slate red	655	lime	2510		
shale red	675	shale blue	2570		
lime	685	lime water	2575		
shale red	697	shale blue	2650		
lime	702	lime	2653		
sdv shale red	737	lime	2655		
shale red	860	lime	2730		
shale blue	865	shale grey	2740		
lime	910	lime	2773		
shale red	1010	shale grey	2790		
shale blue	1055	lime oil 2835 60 bbls	2905		
shale red	1110	shale brown and green			
shale blue	1175	Top of Oswald Horizon	2917		
lime	1185	2917 equals 2925' 6 corrected Meas.			
shale blue	1235	Oswald lime	2927		
shale blue & salt	1283	S.L.M. 2927 equal	2931		
salt	1485	lime oil	2959 TD.		
salt	1490				
shale blue	1500	<u>FIRST DEEPENING RECORD.</u>			
lime shell	1505				
shale blue	1511	Old T.D.	2959		
lime	1580	Comm. 6-26-26 Comp.	7-10-26		
lime	1590	Production 120 bbls per day.	swabbed		
shale grey	1600	lime	2959-3090		
lime	1604	lime Oil	3102 TD.		
shale pink	1620				
lime	1650	<u>SECOND DEEPENING RECORD.</u>			
lime	1688				
shale blue	1695	Old T.D.	3102		
shale red	1725	Comm. 7-18-28 Comp.	8-5-28		
lime	1745	Production Swabbed 83 bbls per day.			
lime	1850				
shale blue	1865	lime brown	3102- 3105		
lime	1885	sdv lime	3108		