

8-12-15W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas


Company - S. S. & Y. LEASE
Farm - Ed Oswald No. 2

Plotted Texas CO
SEC. 8 T. 12 R. 15W
NE SW SW

DEEPENING RECORD

Total Depth. 3243
Comm. 10-20-24 Comp. 1-1-25
Shot or Treated.
Contractor. Stearns-Streeter Company
Issued. 9-16-50

County. Russell
KANSAS



CASING:

15 1/2" 426' 6" 2785'
12 1/2" 894' 5 3/16" 2926', Lowered 2938'
10" 1521
8 1/4" 2490, UR 2433-90'

Elevation. 1859

Production. 250 bbls. oil

Figures Indicate Bottom of Formations.

surface yellow	20	lime wh	1715	lime wh mod	2922
shale blue	160	shale red	1774	shale blue	2926
redrock	177	slate sand wh	1786	shale brown	2933
shale blue	258	slate wh	1817	shale gr	2938
sand grey, W	269	lime grey med	1839	oil sand wh mod	2957
shale br	388	shale blue	1852	shale blue brown	2959
sand fine lt	401	lime wh	1873	lime sand br	2988
iron pyrites & sand	417	slate red	1882	sandy lime	3015
slate blue	426	lime grey	1898	second pay zone	3028
shale lt br	434	slate wh	1922	lime	3109
lime dk	438	lime wh	1938	Total Depth	
lime shell grey	451	lime wh	1952	Remarks:	
shale sandy blue W	456	shale red	1964	Hole full of water 260'	
water sand dark, W	465	shale lt	1983	4 bailers wtr 451'	
shale blue	469	lime wh	1991	Hole full wtr 465'	
lime grey	472	shale brown	2024	Showing of wtr 1127'	
slate blue	476	lime grey	2034	3 bailers of wtr per hr	
iron pyrites yellow	480	lime pink	2066	at 2408'	
shale sandy blue	516	slate red	2088	1 bailer of wtr per hr at	
lime sharp grey	523	lime grey	2104	2595'	
shale sdy wh	542	shale red	2146	Showing of oil at 2675'	
lime wh	544	lime grey	2179	Oil at 2938'	
slate red	645	shale brown	2189		
lime red	667	lime wh	2198		
slate red	726	shale blue	2219	<u>DEEPENING RECORD</u>	
sand corase grey	732	lime grey	2239	Company Sohio Petr.Co.	
redrock	740	slate sdy wh	2248	Comm. 2-12-47	
lime wh	746	lime grey	2272	Comp. 4-16-47	
shale red	796	slate wh	2286	Prod. 50 BOPD-No wtr	
water sand br	800	slate blue	2320	OTD 3109	
shale red	841	lime grey	2344		
sand.wtr lt	849	shale blue	2408	RUST To DD	
shale red	879	shale sdy blue W	2427	DD 3230	
iron yellow	883	shale blue	2437	Total depth	
slate blue	885	lime wh	2445	FU 800' oil, no time	
slate wh	894	shale lt	2459	Ran 345' 4 1/2" liner at	
lime broken wh med.	898	gas sand lt	2473	3204 (Top 2859) WOC (No	
lime wh	936	slate wh	2488	record Pipe) 46' 3" liner	
shale red	1036	lime grey	2497	at 3230. DP & DD.	
shale brown	1094	shale blue	2502	Reagan 3235.	
shale red	1127	lime wh	2505	TD 3238	
shell sdy br, W	1143	slate blue	2591	SW 4 1/2 BOPH 4 hrs.	
slate red	1192	sand wtr grey, W	2597	DD 3243	
slate sdy brown	1204	shale blue	2620	Total depth 3243	
lime wh	1207	lime grey	2626	SW 3 1/2 BOPH/8 hrs.	
shale sdy brown	1228	shale blue	2674	Run T & R. POP.	
shale & salt blue	1274	lime grey, oil	2742		
salt rock grey med.	1504	slate blue	2752	Lansing	2938
shale blue	1521	lime wh	2774		
lime shell grey	1523	slate wh	2780		
slate blue	1579	lime grey	2844		
lime grey	1586	shale blue	2853		
slate wh	1602	lime wh	2866		
lime wh	1606	slate wh	2873		
slate wh	1627	lime br mod	2891		
slate red	1654	shale blue	2904		
lime wh hard	1659	lime wh med	2906		
shale brown soft	1680	slate blue	2914		