

8-12-15W
Plotted Texas CO.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. NW SE NW

DEEPENING RECORD.

Sec 8 T. 12 R. 15W

Casing Record.

10" 2060'9 Farm. Oswald DEC 8 1934

County. Russell.

20" 11'6 8" 2581' Company. Mid West Exploration Co. No. 22 16


15" 101'1065/8" 2916' Contr.

12" 85'1053/16" Comm. 1-18-26

Comp. 3-24-26

Total Depth. 3245 Shot Quarts Between

Correspondence Regarding This Well Should Be Referred To.



Elevation. 1330.9

Figures Indicate Bottom of Formations.

Date Issued. 12-8-34

Initial Production.

215 bbls T.D. 3018

New Prod.-25 bbls on SwabTD 3154

Formation	Depth	Formation	Depth.	Formation	Depth.
surface soil	12	lime white	1980	lime soft	2994
shale blue	90	shale red	1990	lime hard	3000
shale brown	95	broken lime	2025	lime soft brown oil	3005
shale blue	150	lime	2030	lime	3009
shale white	200	shale red	2065	lime hard	3018
shale red	230	lime	2085	T.D.	
shale grey	240	shale blue	2090		
water sand grey	250	lime	2140	DEEPENING RECORD.	
shale red	312	shale blue	2150		
sand	380	lime and shale blue	2190	Old T.D.	3018
shale blue	405	shale blue	2200		
iron	407	lime	2220	Comm. 12-5-29.	
shale blue	415	broken lime and shale		Comp. 1-31-30.	
lime white	417	grey	2280		
shale blue	432	lime hard	2290		
water sand grey	445	lime	2295	Prod. 25 bbls on swab.	
shale blue	490	shale light	2340		
shy shale light	495	shale brown water	2370	lime 3018-	3036
shale blue	530	shale blue	2410	shale blue	3039
shy shale light	565	lime white	2422	lime	3057
shale red	710	shale grey	2427	lime broken shale	3073
water sand	725	shell	2430	red rock	3077
shale red	835	gas sand	2440	lime shells & shale	3082
lime	900	shale blue	2460	lime sdy	3088
shale red	1005	lime	2470	lime light	3105
shale brown and shale		shale blue	2480	red rock	3114
red	1115	broken lime & shale	2520	lime	3120
shale red	1160	lime white	2525	lime oil & gas	3123
lime white	1170	shale blue	2550	shale blue	3126
shale blue	1215	water sand sh oil	2560	lime light	3131
lime brown	1230	shale blue	2590	lime broken	3132
shale blue and salt	1335	lime	2600	lime shells	3134
salt	1470	shale blue	2610	shale white	3140
shale blue	1480	lime	2631	lime	3145
lime with shale breaks	1495	shale blue cave	2636	lime sdy water	3154
shale blue	1500	lime sh oil	2654	TD	
lime	1510	shale blk	2659		
shale blue	1540	broken lime	2740		
lime white	1575	broken lime and blue		Plugged back to 3140	
broken lime and shale	1585	shale	2890	ST. NOLIND OIL AND GAS.	
shale pink	1595	broken lime	2900	DEEPENING RECORD.	
				Old T.D.	3154
				Comm. 12-5-29.	
shale red	1715	shale red	2910	Comp. 1-31-30.	
lime	1730	shale green	2915	Prod. Pet. 50 B.O. 75 EW	
broken lime and		shale green & brown	2926	LIME 3154-	3185
light shale	1755	top of Oswald lime	2926= 2916	red rock	3190
broken lime	1805	corrected measurement.		shale	3200
lime shells and		lime	2934	lime	3206
light shale	1830	shale blue	2940	lime	3211
broken lime and		lime	2945	red rock	3215
grey shale	1895	lime hard dry	2958	sand Gorman	3220
lime white	1905	lime soft	2977	Increase oil.	
broken lime and		lime grey coarse oil	2983	granite	3245
shale red	1930	lime hard & blue	2989	Total Depth.	