

Plotter J. S.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted Texas CO.

Location SW c NW/4
330' fr WL 330' fr SL

Sec. 8 T. 12 R. 15W.

8-12-15W
FEB 6 1933

Casing Record
10" 2395


Farm- Ed. Oswald No. 21 (DRL)

20" 20 8"
15 1/2" 405 65/8"
12" 866 53/16"

Company- Midwest Exploration Co.
Contr.-
Comm.- 7/2/25. Comp.- 9/10/25.

Total Depth 3200'

Shot Quarts Between



Correspondence Regarding This Well Should Be Referred to

Elevation

Figures Indicate Bottom of Formations.
Date Issued. 2-4-33

Initial Production
Est. 100 bbls. TD 3003
Swab 52 B. 24 hr T.D. 3128
New Prod. - 53 bbls. swabbed TD 3200

DEEPENING RECORD

Formation	Depth	Formation	Depth
surface	36	blue slate	2390
blue shale	125	blue shale	2403
blue shale	165	lime	2425
slate	185	sand	2455
blue shale	200	blue shale	2460
red rock	240	lime	2500
slate	250	slate	2505
red rock	320	lime 1 B	2545
sand water	390	slate	2590
blue shale	400	lime	2600
shale blue	410	slate	2605
sand water	465	lime	2790
blue shale	470	slate	2800
blue shale	495	lime	2896
white sand	510	(2895' little wtr-about 5 bbls. per day.)	
lime	520		
blue shale	525	brown shale	2905
lime	545	blue shale	2910
red rock	585	Oswald lime no oil	2917
blue shale	590	Oswald lime 1st pay	2921
lime	605	white sand water	2924
red rock	775	drk lime	2926
blue shale	780	gray lime	2933
lime	805	shale & mud break	2939
blue shale	835	hrd lime cap	2940
red rock	873	sandy lime-oil 2nd pay	2943
lime	915	130 bbls.	
red rock	1145	sandy lime	2952
blue shale	1180	3rd pay lime	2962
salt	1540	lime	3004
lime	1580	4th lime pay	3008
slate	1590	lime	3040
red rock	1605	lime brkn	3073
lime	1615	lime	3074
slate	1620	sdy lime	3078
lime	1630	brkn lime	3083
slate	1645		
lime	1685	Total Depth	3083'
red rock	1720		
lime	1740		
slate	1750		
lime	1775		
slate	1815		
lime	1840		
red rock	1865		
lime	1885		
blue shale	1900		
lime	1915		
red rock	1925		
lime	1970		
white shale	1975		
red rock	1995		
lime	2010		
lime	2020		
white shale	2035		
red rock	2070		
lime	2085		
white shale	2150		
lime	2215		
blue shale	2300		
lime	2340		
brown shale	2360		
water sand	2380		

OVER

Mid west Ed. Oswald Number 31. SW 1/4 NW 12-15W. Russell County.

DEEPENING RECORD. By Mid West.
Old T.D.
Comm. 2-28-28 Comp. 3-15-28.

3083

Prod. Swabbed 52 bbls 24 hours.

No production before Deepening.

lime	3083-	3093
red rock		3099
sdv lime		3102
lime		3110
lime shells and shale		3112
shale blue		3118
sdv lime oil		3122
lime		3128
T.D. 6" 2910.		

DEEPENING RECORD (SECOND) By Stanolind Oil and Gas Co.

Old T.D.
Comm. 1-5-33 Comp. 1-31-33.
Prod. 53 bbls swabbed.

3128

6" 2910.

well practically dead with small amount of water showing
swabbed 44 bbls water while C.O.

lime hard grey	3128-	3140
shale blue		3148
broken lime		3173
lime hard grey		3175
broken lime		3185
Porus lime oil		3186

hole caving badly. Filled up 1200' with oil in 13 hours.
Swabbed 100 bbls in 24 hours on Jan 11, 1933.

lime porus		3192
conglomerate		3197
granite red		3200

T.D.
310'5" liner set to shut off cave.