


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- RUDY HERMAN OIL OPERATIONS
Farm- Meckel "A" No. 1

SEC. 29 T. 12 R. 15W
SE NE SE

Total Depth. 3300'
Comm. 9-25-58 Comp. 10-4-58
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 2-4-61

County Russell
KANSAS



Elevation. 1818' DF

Production. 91 BOPD

CASING:

8 5/8" 200' cem w/132 sx.
5 1/2" 3295' cem w/125 sx.

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

2704-2707 scattered rich brn oil stain in buff to brn sucrose limestone

2896-2899 rare lgt brn oil stain in buff crystalline and chalky limestone

2947-2950 rare lgt brn oil stain in buff crystalline and sucrose limestone

2978-2983 rare lgt brn oil stain in buff to white fine crystalline limestone

3002-3005 rare lgt brn oil stain in buff crystalline & sucrose limestone

3017-3022 rare lgt brn oil stain in buff crystalline & matted oolitic limestone

3047-3049 rare lgt brn oil stain in buff.

3059-3061 crystalline limestone

3066-3075 white oolitic limestone carrying very rare spotted lgt brn oil stain.

3136-3139 dense buff crystalline limestone carrying very rare traces of lgt brn spotted oil stain

3231-3235 occasional lgt brn oil stain in buff sucrose & buff crystalline limestone

3242-3300 vari-colored sharp cherts w/rare trace of clear and pink, round, clear & frosted, medium-grained sand grains
Rotary Total Depth 3300'

DST #1 2957-2990', op 1 hr, fair blow thruout test, rec. 30' gas in pipe, 5' slightly oil-cut mud & 25' mud. IFP 0#, FFP 0#, BHP 115#/20 mins.

DST #2 2992-3012', op 1 hr, strong blow thruout test, rec. 1005' gas in pipe, 60' oil & gas cut mud, 55' heavy oil & gas cut mud w/some free oil. IFP 0#, FFP 0#, BHP 455#/30 mins.

DST #3 3013-3025', op 30 mins, weak blow for 2 mins, rec. 10' rotary mud, IFP 0#, FFP 0#, BHP 150#.

TOPS: SAMPLE

Anhydrite (driller)	878
Topeka	2703
Heebner	2924
Toronto	2942
Lansing-Kansas City	2973
Conglomerate	3242