

WELL PLUGGING RECORD

All Information Completely  
Like Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH

	X		

Locate well correctly on above  
Section Plat

Russell County. Sec. 30 Twp. 12S Rge. (E) 15 (W)  
Location as "NE/CNWxSWx" or footage from lines C S/2 N/2 SW/4  
Lease Owner Pan American Petroleum Corporation  
Lease Name L. L. Austin "C" Well No. 1  
Office Address P. O. Box 432 - Liberal, Kansas 67901  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 8-30 19 55  
Application for plugging filed 10-29 19 69  
Application for plugging approved 10-31 19 69  
Plugging commenced 11-6- 19 69  
Plugging completed 11-28 19 69  
Reason for abandonment of well or producing formation depleted to economic limit.

If a producing well is abandoned, date of last production 11-5 19 69  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3322 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dodge	Oil	3008	3010	8-5/8"	960	0
Lansing "A" "B" & "C"	Oil	3044	3076	5-1/2"	3321	2328

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug back with sand from 3294-3000.  
Spotted 5 Sx. cement plug 3000-2970.  
Plug back with mud from 2970-960.  
Spotted 2 Sx. cement plug gel mud to 370.  
Cement and rock to 350.  
Plugged back from 350 to surface with  
5-1/4 yards Ready Mix concrete.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Company  
Address P. O. Box 156 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.  
J. W. VAUGHN

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God,

(Signature) J. W. VAUGHN

P. O. Box 432 - Liberal, Kansas 67901  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 69.

February 11, 1972

Notary Public.

