

October, 1936.

15-167-06282

Not Done

Central Petroleum #1 Ginther,
sw sw SE 19-12S-15W,
Elevation 1841

Pennsylvanian conglomerate. 3331-3345'
3331-3345 True conglomerate of stained chert and sand.

Residuum. 3345-3376'
3345-3353 Dark red clay with included sand. Some weathered
chert, mainly of Viola type. Abundant cavings.
3353-3376 One sample, which may not be representative. Similar
to above.

This well did not reach recognizable Ordovician in place. The
Viola types in the residuum suggest that Viola or Decorah might ??
be present below. To the west, in Sec. 24-12D-16W, a well found
both Viola and Decorah under the Pennsylvanian.