

3-12-15W

DRILLERS' WELL LOG

State Geologist
WICHITA

DATE COMMENCED: June 7, 1978
DATE COMPLETED: June 16, 1978

Graves Drilling Co., Inc.
EULERT -3 #2
SW NE NW
Sec. 3-T12S-R15W
Russell County, Ks.

0 -	40'	Post Rock
40 -	270'	Shale, Clay
270 -	786'	Shale
786 -	825'	Anhydrite
825 -	1315'	Red Bed
1315 -	2357'	Shale & Lime
2357 -	2384'	Lime
2384 -	2604'	Sand, Shale & Lime
2604 -	2804'	Lime & Shale
2804 -	2808'	Shale
2808 -	2873'	Lime & Shale
2873 -	3198'	Lime
3198 -	3210'	Dolomite
	3210'	RTD

ELEVATION: 1721 KB

FORMATION DATA

Anhydrite	786
Tarkio	2357
Sand	2384
Topeka	2604
Heebner	2804
Toronto	2844
Lansing	2873
Arbuckle	3198
RTD	3210

Surface Pipe: Set used 8-5/8",
28#, pipe at 270' with 165
sacks common cement, 2% Gel,
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 19 day of June 1978