

API No. 15 — 167 — 20,738
County Number

Operator

Shields Oil Producers, Inc.

Address

Shields Building Russell, Kansas 67665

Well No.

#1

Lease Name

Eulert "B"

Footage Location

990 feet from (X) (S) line 1650 feet from (X) (W) line

Principal Contractor

Shields Drilling Co., Inc.

Geologist

M. L. Ratts

Spud Date

4-30-75

Total Depth

3178

P.B.T.D.

2412

Date Completed

5-9-75

Oil Purchaser


Koch

S. 4 T. 12 R. 15 ^NW

Loc. NW SE SW

County Russell

640 Acres
N



Locate well correctly

Elev.: Gr. 1689

DF 1691 KB 1693

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	820	Quickset	425	
Production	7 7/8	4 1/2	9 1/2	2449	Common	75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jet	2357-2362
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture w/15,000#Sd to 225 BBL Water	2357-2362

INITIAL PRODUCTION

Date of first production 7-22-75		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 20 bbls.	Gas MCF	Water 220 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) None			Producing interval(s) 2357-2362		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Shields Oil Producers, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Eulert "B"	Oil
S 4 T 12 R 15 E W		

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
D. S. T. #1 2336-2390 Fair blow for 1 hr. Rec. 400' of Oil and Gas Cut Mud. I. S. I. P. - 739#/30min. I. F. P. - 91# F. F. P. - 240# F. S. I. P. - 739#/30min.			Anhydrite Grandhaven Lm. 1st Tarkio Sd. Tarkio Lm. 3rd. Tarkio Lm. Elmont Lm. Topeka Lm. Heebner Sh. Toronto Lm. L-K. C. Lm. Sh. Cong. Cherty Cong. Reworked Arb.	752 2254 2264 2328 2356 2382 2570 2793 2812 2844 3126 3148 3164
D. S. T. #2 3146-3172 Weak blow for 5 min. Rec. 5' of mud. I. S. I. P. - 87#/30min. I. F. P. - 44#				
D. S. T. #3 (Straddle test) 3030-3038 Weak blow for 7 min. Rec. 5' mud. I. S. I. P. - 76#/30min. I. F. P. - 34#				



USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature  Date 7-21-75 Date
---------------	---

93786