

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 4 T. 12 R. 15 ^E/_W

API No. 15 — 167 — 20,888
County Number

Loc. SW SE SW

County Russell

Operator
Shields Oil Producers, Inc.

Address
Shields Building Russell, Kansas 67665

Well No. #6 Lease Name Eulert "B"


Footage Location
330 feet from (N) (S) line 1650 feet from (E) (W) line

Principal Contractor Shields Drlg. Co., Inc. Geologist M. L. Ratts

Spud Date 7-7-76 Total Depth 2450 P.B.T.D. 2424

Date Completed 7-12-76 Oil Purchaser Koch

640 Acres
N



Elev.: Gr. 1690

DF 1692 KB 1695

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	535	Quickset	375	
Production	7 7/8	4 1/2	10 1/2	2430	Common	75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jet	2357-2361

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture w/380 B.W. & 20,000# Sand	2357-2361

INITIAL PRODUCTION

Date of first production <u>7-22-76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil <u>25</u> bbls.	Gas <u>Yes</u> MCF	Water <u>25</u> bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold) <u>Used</u>			Producing interval (s) <u>2357-2361</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 644.

Operator
Shields Oil Producers, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 6	Lease Name Eulert "B"	Oil
S <u>4</u> T <u>12</u> R <u>15</u> E <u>4</u>		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>No D.S.T.'S</u>			Anhydrite	750
			Grandhaven Lm.	2254
			Tarkio Sd.	2266
			Dover Lm.	2286
			Tarkio Lm.	2328
			Brd Tarkio Sd.	2358
			Elmont Lm.	2381

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="text-align: center;"><u>M. Zatta</u> Signature</p> <p style="text-align: center;"><u>Production Engineer</u> Title</p> <p style="text-align: center;"><u>7-27-76</u> Date</p>
---------------	---

16266