

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted Texas CO.

Location SW c NE
330' fr SL 330' fr WL

Sec. 5 T. 12 R. 15W.

5-12-15W
County- Russell, FEB 19 1929

Casing Record

10" 1349 Farm- Brummitt No. 1
20" 135 8" Company- The Carter Oil Co.
15" 376 65/8" 2555 Contr.-
12" 760 53/16" 2798 1/2 Comm.- 8/28/25. Comp.- 10/13/25.
Total Depth 2846' Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Elevation 1678

Figures Indicate Bottom of Formations.
Date Issued. 2/16/1929. DEEPENING RECORD

Initial Production 125 bbls
natural.

Formation	Depth	Formation	Depth
sand	50	blue shale	1690
red rock	95	lime	1725
sand HFW	105	red mud	1735
slate	125	lime	1750
shale Set 20" csg.	135	sandy shale little wtr	2395
blue mud	160	shale	2435
blue shale HFW	140	sandy lime	2445
sand	235	shale	2465
blue shale	245	lime water	2475
blue mud	265	shale	2490
blue shale	285	sandy lime wtr	2510
sand	295	blue shale	2513
blue shale	325	lime	2535
iron	330 ✓	Set 6 5/8" csg. 2498'	
shale	340	shale	2555
sand	350 ✓	lime	2570
iron	353 ✓	Light show oil 2518'	
red sand	360	shale	2590
iron	376 ✓	lime	2610
Set 15 1/2" csg. SLM		shale	2615
red mud 12 BW	396	lime	2645
red sand	416	shale	2650
red mud	425	lime	2660
red rock	535	lime	2700
red mud	580	shale	2715
sand HFW	595	lime	2738
red rock	630	coal	2745
red mud	655	lime	2750
red rock	705	shale	2758
red mud	710	lime	2779
lime Set 12 1/2" csg SLM	760	Set 5 3/16" csg.	
red rock	765	lime	2780 1/2
red rock	800	drk red rock	2786
red mud	850	Lowered 5" to set at 2790'	
red rock	875	slate	2790
blue shale	910	lime Oil & gas	2793
red rock	930	lime More oil	2798 1/2
red mud	960	lime	2812
red rock	1000	slimey mud	2824
blue shale	1055	lime white	2836
salt	1325	lime	2846
shale	1349	Total Depth 800' wtr.	2846'
Set 10" csg. SLM			
lime	1355		
blue shale	1360		
lime	1370		
blue shale	1380		
lime	1395		
shale	1410		
lime	1415		
blue shale	1425		
lime	1435		
shale	1450		
brkn lime	1470		
lime	1495		
red rock	1510		
lime	1540		
red mud	1600		
brkn lime	1635		
lime	1680		