

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


5-12-15W

Company - L. A. FARRIS
 Farm - Brummitt No. 1

SEC. 5 T. 12 R. 15 W
 SW NW NE

Total Depth. 3187=3183' Corr. DF
 Comm. 4-18-47 Comp. 5-2-47
 Shot or Treated.
 Contractor.
 Issued. 6-28-47

County. Russell
 KANSAS



CASING:

8 5/8" 587' Cem. w/275 sx.
 5 1/2" 3182' Cem. w/175 sx.

Elevation. 1744.00 ft

Production. Est. 75 B.

Figures Indicate Bottom of Formations.

surface clay	15
sand	70
sand & shale	120
shale	180
shale & shells	270
sand	300
shale & shells	480
shale & red bed	790
anhydrite	830
shale & red bed	900
red bed, shale & shells	1210
salt & shale	1395
lime & shale	1695
lime	1760
lime & shale	1860
lime	1900
shale & lime	2560
lime	3172
conglomerate	3183
sand	3187

Corr. 3187= 3183 DF.
 Total Depth.

Tops:

Topeka	2549
Lansing K. C.	2861
Conglomerate	3172
Gorham Sand	3183