

Plotted Texas CO. 5-12-150-  
 J.R.S.


MUDDY OIL COMPANY.  
 Kollman No. 1

SEC. 5 T. 12 R. 15W  
 SEC SW NW

DEEPENING RECORD.

Total Depth. 2841 P.B. 2818  
 Comm. 4-8-25 Comp. 6-23-25  
 Shot or Treated.  
 Contractor.  
 Issued. 3-31-34

County. Russell. MAR 31 1934



Elevation.

Production. 14 bbls.,

Figures Indicate Bottom of Formations.

lime and gravel	91	shale blue	2400
fresh water at 40		Water at 2410	
red rock	111	lime blue	2445
shale grey	141	shale blue	2460 cave.
red rock	161	lime blue Oil show	2490
shale grey	170	shale blue	2520
sand	225	lime grey	2550
HFV 180		shale blue	2560 cave
shale brown	230	lime white	2630
shale grey	260	oil show at 2570	
lime white	265	shale blue	2635
small amount of Iron.		lime grey	2645
sand shale lime	270	oil show 2645	
shale grey	290	lime light	2680 Oil show.
sand grey	330	shale grey	2717
sand white	360	lime white	2732
red rock	710	shale blue	2741
HFV 620		shale brown	2746
lime grey	750	shale green	2754 SIM
red rock	880	lime white	2755 1/2 Oil
shale brown	900	lime brown and Pay	2756 1/2
red rock	1000	lime grey	2757 1/2
shale brown	1070	lime light and Pay	2759 1/2
salt	1290	lime light	2762
slate blue	1310	TD.	
red rock	1450	Swabbed 12 1/2 bbls at 2755 1/2	
shale grey	1460	Swabbed 10 bbls at 2757 1/2	
Gas at 1460 to 1465		Swabbed 12 bbls at 2759 1/2	
lime grey	1465	Swabbed 14 bbls at 2762	
shale grey	1475		
red rock	1485		
lime grey	1520		
red rock	1600		
lime grey	1675		
lime dark	1715		
lime grey	1760		
shale blue	1800		
lime grey	1840		
lime grey	1860		
red rock	1875		
lime light	1950		
red rock	1960		
sdylime	1965 wtr		
lime grey	1970		
shale grey	2000		
lime blue	2025		
shale blue	2095 cave		
shale brown	2140		
lime grey	2145		
shale blue	2170		
lime blue	2200		
shale blue	2235 cave		
shale blue	2240		
lime white	2260		
gas sand	2272		
Est 1,500,000 cu ft gas.			
shale blue	2300		
lime white	2335		
		lime	2762- 2783 1/2
		lime shells	2790
		lime hard	2793
		lime med	2796
		lime Oil	2800
		lime hard	2802
		Swabbed 7 B.	
		lime white	2822
		sand lime gr	2826
		lime	2841 3 BW
		TD.	
		P.B. 2818	

DEEPENING RECORD.

Old T.D. 2762

Before Deepening 35 B.P.D. and  
 after deepening 120 B.P.D.