

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


5-12-15W

Company - F.C. JOHNSON ESTATE
Farm - Kollman No. 8

SEC. 5 T. 12 R. 15 W
CWL SE NW

Total Depth. 3086' RTM
Comm. 12-29-43 Comp. 2-20-44
Shot or Treated.
Contractor. B&R Drlg. Co.
Issued. 7-29-44

County. Russell
KANSAS



CASING:
8 5/8" 721' Cem.
5 1/2" 3062' Cem.

Rotary O-3071
Cable 3071-86

Elevation. _____

Production. Pot. 125 B.
No wtr

Figures indicate Bottom of Formations.

sand & clay	43
shale & sand	235
shale & shells	250
sand	260
shale	273
shale & shells	279
shale & sand	370
shale	375
shale & sand	430
hard sand & iron	455 ✓
shale	475
red shale	696 ✓
iron	707 ✓
anhydrite	740
shale & shells	1010
shale	1425
shale & shells	1445
shale & lime	1556
shale & shells	1640
lime	1723
lime & shale	2061
shale	2206
lime & shale	2297
lime	2335
lime & shale	2427
lime	2663
lime & shale	2840
lime	2855
lime & shale	2938
lime	2978
lime & shale	3065
lime	3069
sand	3071

TD Rotary hole
granite wash & granite 3086
Total Depth. RTM

Tops: (Rot. Table Meas.)

Topeka	2470
Heebner	2708
Dodge	2711
Douglas	2736
Lansing KC	2757
Gorham Sand	3062
Reagan Sand	3066

Ran Lane Wells Gamma Ray-Neutron Log
in open hole at TD 3071 RTM
Perf. w/Lane Wells - 36 holes
3059-73 no shows
Set Lane Wells Bridge Plug @ 3025
Perf. w/Lane Wells w/24 shots 2961-71
Perf. w/Lane Wells w/12 shots 2993-98
no shows of oil or wtr after
perf. from 2961-71 or 2993-98
Acidized w/2000 Gals. thru csg
Initial prod. 125 BO & no wtr, 1st 24
hours pumping after 2000 gal.
acid