

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


5-12-15W

Company - T. C. JOHNSON ESTATE
Farm - R. Kollman No. 9 (Twin #5)

SEC. 5 T. 12 R. 15 W
NW NE NW

Total Depth. 3138'
Comm. 3-26-46 Comp. 4-23-46
Shot or Treated.
Contractor. Biddle Drlg. Co.
Issued. 10-5-46

County. Russell
KANSAS



Elevation. 1733 ft

Production. 100 BO, no wtr.

CASING:

8 5/8" 780' Cem.
5 1/2" 3124' Cem.

Figures Indicate Bottom of Formations.

sand & shale	285
shells & shale	320
sand & shale	470
red bed & shale	600
red bed	768
anhydrite	776
lime	788
anhydrite	830
shale & shells	1160
salt & shale	1260
salt	1370
shale & anhydrite	1430
shale & lime	1720
lime	2005
lime & shale	2092
lime	2149
lime & shale	2370
shale	2480
shale & lime	2602
lime	3138
Total Depth.	

Tops:	
Dodge limestone	2788
Trans.-K.C.	2819
Base Kans. City	3099
Arbuckle	3124