


5-12-15W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company. SOHIO OIL CO., ET AL  
Farm. Sutton SWDW No. 1

SEC. 5 T. 12 R.15W  
SW NE SE

County Russell  
KANSAS



Elevation. 1674' DF

Production. SWDW

Total Depth. 3368'  
Comm. 11-30-56 Comp. 12-10-56  
Shot or Treated.  
Contractor. Aylward Drlg. Co.  
Issued. 4-13-57

CASING:

8 5/8" 737' w/400 sx cem.  
5 1/2" 3140' w/100 sx cem.

Figures indicate Bottom of Formations.

sand-gravel	190
sand-gravel w/shale	
strks	270
shale-shells-iron	275 ✓
iron-sand	288 ✓
shale-sand	435
red bed-shale	728
Anhydrite lime	745
shale-shells	1490
brkn lime	1565
lime-shale	1710
lime	1830
brkn lime	1960
lime-shale	2205
shale-shells	2375
shale-lime	2636
brkn lime	2665
shale-lime	2815
lime	3180
lime-sand	3265
sdv lime	3308
lime	3362
sand-granite wash	3368
Total Depth	

TOPS:

Topeka	2504
Heebner	2756
Lansing/Kansas City	2810
B/Kansas City	3108
Cherty Conglomerate	3122
Arbuckle	3134
Granite Wash	3364