

State Geological Survey
WICHITA BRANCH

DRILLERS' WELL LOG

15-167-20891

9-12-15W

DATE COMMENCED: May 3, 1976
DATE COMPLETED: May 7, 1976

Louis M. Mai
BRUNDAGE # 5
NE SE NW of Sec 9-T12S-R15W
Russell County, Kansas

ELEVATION: 1690 K.B.

0 - 36'	Surface Soil, Clay and Sand
36 - 205'	Shale, Sand Streaks and Post Rock
205 - 367'	Sand
367 - 553'	Red Bed and Shale
553 - 743'	Red Bed
743 - 782'	Anhydrite
782 - 795'	Shale and Shells
795 - 1400'	Red Bed and Shale
1400 - 2548'	Shale and Lime
2548 - 2570'	Lime
2570 - 2580'	Shale and Sand
2580 - 2804'	Lime
2804 - 2808'	Shale
2808 - 2840'	Lime
2840 - 2855'	Shale
2855 - 2960'	Lime and Shale
2960'	RTD

FORMATION TOPS

Anhydrite	743
Howard	2548
Severy	2570
Topeka	2580
Heebner	2804
Toronto	2826
Douglas	2840
Kansas City	2855
RTD	2960

SURFACE PIPE:

Set 551' of used 8 5/8", 28# pipe
w/285 sacks Common, 2% Gel, 3% cc.

PRODUCTION PIPE:

Ran used 14#, 5 1/2" casing @ 2959
w/250 sacks 50/50 Pozmix,
w/18% salt & .75% CPR2 and 1/4
Flo-seal per sack.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 10th day of May, 1976.