

15-167-20892
9-12-15W

State Geological Survey
WICHITA BRANCH
DRILLERS' WELL LOG

DATE COMPLETED: May 8, 1976
DATE COMPLETED: May 14, 1976

Leslie M. Mai
FOUNDATION # 6
ST. NO. of Log: 9-T125-015W
Russell County, Kansas

ELEVATION: 1718 K.B.

0 - 228'	Surface Soil, Shale, Post Rock
228 - 460'	Sand
460 - 770'	Shale and Red bed
770 - 808'	Anhydrite
808 - 1425'	Shale
1425 - 2566'	Shale and Lime
2566 - 2589'	Lime
2589 - 2596'	Shale
2596 - 2621'	Lime
2621 - 2625'	Shale
2625 - 2841'	Lime and Shale
2841 - 2856'	Lime
2856 - 2871'	Shale and Lime
2871 - 3168'	Lime and Shale
3168 - 3230'	Dolomite
3230'	RTD

FORMATION DATA

Anhydrite	770
Howard	2566
Severy	2589
Topoka	2596
Rechnor	2621
Toronto	2841
Douglas	2856
Kansas City	2871
Arbuckle	3168
RTD	3230

SURFACE PIPE:

Set used 23#, 8 5/8", pipe @
558' w/285 sacks Common, 2% Gel,
3 1/2 cc.

PRODUCTION PIPE:

Ran used 11 1/2", 5 1/2" casing @ 3228'
w/300 sacks 50/50 Pozmix w/18%
salt & .75% CFB2 and 1/2" Flo-seal
per sack.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 17th day of May, 1976.

Heavily M. Hague
Notary Public