


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PEEL-HARDMAN OIL
Farm- Sutton No. 2

SEC. 9 T. 12 R. 15W
SE NE SW

Total Depth. 3188'
Comm. 5-7-58 Comp. 5-15-58
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 7-26-58

County Russell
KANSAS



Elevation. 1731' KB

Production. Dry

CASING:

3 5/8" 730' cem.
5 1/2" 3183' cem.

Figures indicate Bottom of Formations.

surface soil & shale	125
shale & shells	320
flint rock	335
shale	355
sand	460
shale & red rock	695
lime	730
red bed	775
Anhydrite	805
red bed & shale	1280
shale	1435
lime	1445
shale & lime	1620
lime	1875
shale & lime	2640
lime	2714
shale & lime	2810
lime	2935
shale & lime	3015
lime	3185 RTD
lime	3188
Total Depth	

TOPS:

Anhydrite	775
Topeka	2609
Heebner	2830
Toronto	2850
Lansing	2880
Arbuckle	3180

Perf. from 3164-70 and 3170-75, 25 shots
each zone. Acidized w/500 gals.
Perf. 25 holes from 2924-2929, acidized
w/1000 gals. Perf. from 2905-10, acidized
w/1500 gals. Acidized w/1000 gals.