

State Geological Survey
WICHITA, BRANCH

DRILLERS' WELL LOG

DATE COMMENCED: December 8, 1975
DATE COMPLETED: December 14, 1975

Louis M. Mai
SUTTON # 3
SE SW NW of Sec 9-T12-R15 W
Russell County, Kansas

ELEVATION: 1791 K.B.

FORMATION TOPS

0 - 100' Post Rock, Clay, Sand
100 - 195' Shale, Sand Streaks
195 - 519' Sand & Shale
519 - 621' Red Bed and Shale
621 - 842' Red Bed and Sand Streaks
842 - 883' Anhydrite
883 - 1185' Red Bed and Shale
1185 - 1615' Shale, Shells
1615 - 2616' Lime and Shale
2616 - 2650' Lime
2650 - 2660' Shale and Sand
2660 - 2881' Lime
2881 - 2885' Shale
2885 - 2916' Lime
2916 - 2932' Shale
2932 - 3050' Lime
3050' RTD

Anhydrite	842
Howard	2616
Severy	2650
Topeka	2660
Haebner	2881
Toronto	2902
Douglas	2916
Kansas City	2932
RTD	3050

SURFACE PIPE:

Set 618' of used 8 5/8", 28#
pipe w/300 sacks Common, 2% Gel,
3% cc.

PRODUCTION PIPE:

Ran 15#, 5 1/2" new casing @ 3049'
w/250 sacks 50/50 Pozmix, w/18%
salt CFR 2 and Floseal.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 16th day of December, 1975.

Kathleen M. Hogue
Notary Public