

9-12-15W

State Geological Survey

WICHITA, BRANCH

DRILLERS' WELL LOG

DATE COMMENCED: December 21, 1975

DATE COMPLETED: January 4, 1976

MAR 17 1977

Louis M. Mai

SUTTON # 5

NW SW NW of Sec 9-T12-R15W

Russell County, Kansas

ELEVATION: 1739 K.B.

FORMATION TOPS

0 - 70' Surface Soil and Post Rock
70 - 238' Shale, Sand Streaks
238 - 527' Sand, Hard Sand, Red Bed
527 - 792' Red Bed
792 - 829' Anhydrite
829 - 2578' Shale and Lime
2578 - 2600' Lime
2600 - 2610' Shale
2610 - 2831' Lime
2831 - 2835' Shale
2835 - 2855' Shale and Lime
2855 - 2864' Lime
2864 - 2884' Shale
2884 - 3000' Lime
3000' RTD

Anhydrite 792
Howard 2578
Severy 2600
Topeka 2610
Heebner 2831
Toronto 2855
Douglas 2864
Kansas City 2884
RTD 3000

SURFACE PIPE:

Set new 20#, 8 5/8" pipe @
527' w/285 sacks Common, 2% Gel,
3% cc.

PRODUCTION PIPE:

Set new 15#, 5 1/2" casing @
2999' w/250 sacks 50/50 Pozmix
w/18% salt, .75% CFR2 & Floseal.

RECEIVED
JAN 12 1976
COMMISSIONER OF GEOLOGY
TOPEKA, KANSAS

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 6th day of January, 1976.

Rebecca M. Hague
Notary Public

My Commission Expires: April 11, 1978