

State Geological Survey
WICHITA, BRANCH

DRILLERS' WELL LOG

15-167-20874

9-12-15W

DATE COMMENCED: April 2, 1976
DATE COMPLETED: April 7, 1976

Louis M. Mai
SUTTON # 7
NW NW NW of Sec 9-T12S-R15W
Russell County, Kansas

ELEVATION: 1727 K.B.

0 - 225'	Surface Soil, Sand, Shale
225 - 315'	Sand
315 - 472'	Sand, Pyrite
472 - 779'	Red Bed, Shale
779 - 815'	Anhydrite
815 - 1780'	Shale, Shells, Lime, Red Bed
1780 - 2564'	Lime, Shale
2564 - 2586'	Lime
2586 - 2596'	Shale
2596 - 2818'	Lime
2818 - 2822'	Shale
2822 - 2840'	Shale and Lime
2840 - 2852'	Lime
2852 - 2872'	Shale and Lime
2872 - 2990'	Lime
2990'	RTD

FORMATION DATA

Anhydrite	779
Howard	2564
Severy	2586
Topeka	2596
Heebner	2818
Toronto	2840
Douglas	2852
Kansas City	2872
RTD	2990

SURFACE PIPE:

Set used 8 5/8" pipe @ 552'
w/300 sacks Common cement,
2% Gel, 3% cc.

PRODUCTION PIPE:

Set used 14#, 5 1/2" casing @ 2989'
w/250 sacks 50/50 Pozmix, 18% salt,
.75% CFR & 1/4# Floseal.

MAY 18 1977

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 12th day of April, 1976.

Alvin M. Nagae
Notary Public

My Commission Expires: April 11, 1978