

15-167-20875
9-12-15W

DRILLERS' WELL LOG

DATE COMMENCED: April 8, 1976
DATE COMPLETED: April 13, 1976

Louis M. Mai
SUTTON # 8
NE NW NW of Sec 9-T12-R15 11
Russell County, Kansas

0 - 55'	Surface Soil, Shale, Sand
55 - 308'	Shale, Shells, Sand
308 - 325'	Hard Sand
325 - 543'	Shale, Red Bed
543 - 760'	Red Bed
760 - 797'	Anhydrite
797 - 1220'	Red Bed, Shale
1220 - 1595'	Shale, Shells, Lime Streaks
1595 - 2160'	Lime, Shale
2160 - 2300'	Lime, Shale, Sand Streaks
2300 - 2465'	Shale, Lime, Sand
2465 - 2545'	Lime and Shale
2545 - 2568'	Lime
2568 - 2577'	Shale, Sand
2577 - 2798'	Lime
2798 - 2802'	Shale
2802 - 2835'	Lime
2835 - 2850'	Shale
2850 - 2975'	Lime
2975'	RTD

FORMATION TOPS	
Anhydrite	760
Howard	2545
Severy	2568
Topeka	2577
Heebner	2798
Toronto	2824
Douglas	2835
Kansas City	2850
RTD	2975

SURFACE PIPE:
Set 541' of used 8 5/8", 28#
pipe @/285 sacks Common, 2% Gel,
3% cc.

PRODUCTION PIPE:
Ran used 1 1/2", 5 1/2" casing @ 2974'
w/250 sacks 50/50 Pozmix w/18% salt
and .75% CFR2 w/1/2# per sack flow
seal

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14th day of April, 1976.

Notary Public

My Commission Expires: April 11, 1978