

State of Kansas
WICHITA COUNTY
DRILLERS' WELL LOG

15-167-20876
9-12-15W

DATE COMMENCED: April 15, 1976
DATE COMPLETED: April 21, 1976

Leonard M. Hall
SECTION # 9
S. 1/2 NW of Sec 9-T12-N15
Russell County, Kansas

ELEVATION: 1740 K.B.

FORMATION TOPS

Anhydrite	790
Howard	2577
Savoy	2600
Topeka	2610
Keokuk	2832
Toronto	2856
Druggins	2871
N.L.	2889
RTD	2919

CEMENT PIPES

Net 567' of used 3 5/8", 20# pipe
w/205 sacks Common, no Gal, 3' cc.

PRODUCED WATER

Run used 104', 2 1/2" casing to 2894'
w/250 sacks 50/50 Pozzux, w/18 1/2
salt sac .75% JMC & SF Rio seal.

0 - 110'	Surface Sand, Post Rock, Shale
110 - 235'	Clay, Shale
235 - 325'	Sand
325 - 337'	Hard Sand and Pyrite ✓
337 - 450'	Sand, Shale Streaks
450 - 790'	Red Bed and Shale
790 - 827'	Anhydrite
827 - 1685'	Shale
1685 - 2577'	Lime and Shale
2577 - 2600'	Lime
2600 - 2610'	Shale and Sand
2610 - 2832'	Lime
2832 - 2836'	Shale
2836 - 2856'	Lime and Shale
2856 - 2871'	Lime
2871 - 2889'	Shale
2889 - 2919'	Lime and Shale
2919'	RTD

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 27th day of April, 1976.

Martha M. Hogue
Notary Public

My Commission Expires April 11, 1978