

DRILLERS' WELL LOG

DATE COMMENCED: December 15, 1975
DATE COMPLETED: December 20, 1975

Louis M. Mai
SUTTON B-8
NE NW SW of Sec 9-T12S-R15W
Russell County, Kansas

ELEVATION: 1800 K.B.

FORMATION TOPS

0 - 95' Surface Soil, Clay, Post Rock
95 - 290' Clay, Sand Streaks
290 - 405' Sand
405 - 506' Shale; Sand Streaks
506 - 850' Red Bed
850 - 891' Anhydrite
891 - 1495' Red Bed, Shale
1495 - 2626' Shale, Lime
2626 - 2660' Lime
2660 - 2671' Shale
2671 - 2892' Lime
2892 - 2896' Shale
2896 - 2913' Shale and Lime
2913 - 2925' Lime
2925 - 2943' Shale
2943 - 3060' Lime
3060' RTD

Anhydrite	850
Howard	2626
Severy	2660
Topeka	2671
Heebner	2892
Toronto	2913
Douglas	2925
Kansas City	2943
RTD	3060

SURFACE PIPE:

Set new 8 5/8", 24# pipe @ 596'
w/ 300 sacks Common cement,
2% Gel, 3% cc.

PRODUCTION PIPE:

Set new 14#, 5 1/2" casing at 3059'
w/250 sacks 50/50 Pozmix, w/18%
salt and .75% CFR2 and Floseal.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 22nd day of December, 1975.

Harvey M. Hague
Notary Public

Commission Expires: April 11, 1978

9-12-15u
NE NW-S4
9-12-15u



K. G. S. L. B. R. A. N. Y.

