

KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

16-12-15w
SW-NW-NW


16-12-1
SW-NW

WILLIAMS WELL LOG

API# 15-167-20,678

DATE COMMENCED: July 23, 1974
DATE COMPLETED: August 3, 1974

Louis M. Noel
JOE KITT #
3 1/4 NW 1/4 NW 1/4
Sec. 16-T123-N15W
Russell County, Kansas



ELEVATION: 1831 L.S.

- G - 110' Foot Rock: & Clay
- 110 - 139' Sand
- 139 - 411' Shale w/streas sand
- 411 - 429' Hard Sand
- 429 - 465' Sand
- 465 - 565' Shale
- 565 - 873' Red Bed
- 873 - 920' Anhydrite
- 920 - 1045' Red Bed
- 1045 - 1475' Shale
- 1475¹⁴⁷⁵ - 2145' Lime & Shale
- 2145 - 2450' Shale
- 2450 - 2701' Shale & Lime
- 2701 - 2919' Lime
- 2919 - 2923' Shale
- 2923 - 2952' Shale & Lime
- 2952 - 2969' Shale
- 2969 - 3219' Lime
- 3219 - 3261' Shale
- 3261 - 3330' Dolomite
- 3330' RTD

FORMATION DATA

Anhydrite	873
Topok	2701
Neohar	2919
Turonto	2923
Douglas	2952
Kansas City	2969
Base Kansas City	3219
Artuckle	3261
RTD	3330



SURFACE PIPE: Set used 2 1/2" pipe at 706' with 175 sacks 60/40 pozzin, 2 1/2 Gal. 2 1/2 cc and 175 sacks cement, 3/4 cc.

PRODUCTION PIPE: Set used 1 1/2", 5 1/2" pipe at 3314' with 350 sacks 50/50 pozzin, 1 1/2 salt sat. with CR-2 & 1/4" Flo-seal.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF RUSSELL) ss.

Larry Curtis of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 9th day of August 1974.

by Comm. Expires
April 11, 1975

Neithy M. Hague
Notary Public