


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS  
Farm- Holland SWD No. 2

SEC. 17 T. 12 R. 15W  
SW SE SW

Total Depth. 3535'  
Comm. 11-18-56 Comp. 12-2-56  
Shot or Treated. 3000 gals.  
Contractor. Shields Drlg. Co., Inc.  
Issued. 3-23-57

County Russell  
KANSAS



Elevation. 1813' RB/

Production. SWDW

CASING:

8 5/8" 895' w/400 sx cem.  
4 1/2" 3335' w/500 sx cem.

Figures indicate Bottom of Formations.

surface clay	25
shale-sand strks	345
sand	440
sand-shale	620
red bed	884
Anhydrite	930
red bed	1050
red bed-salt-shale-	
shells	1545
shale-lime strks	1725
lime-shale	1945
lime	2015
lime-shale	2285
shale-lime strks	2385
shale	2540
shale-lime	2715
lime	3272
sand- conglomerate	3280
lime-chert-shale	3315
lime	3478
lime-s nd	3489
lime-sand-granite	
wash	3535 RTE

TOPS:

Topeka	2713
Heebner	2934
Toronto	2954
Lansing-Kansas City	2986
Gorham sand	3270
Cherty conglomerate	3277
Ero. Arbuckle	3303
Arbuckle	3311
Reagan sand	3460
Granite Wash	3505

DST #1 2885-2920 Open 1 hr.  
w/good weak blow thruout. Rec.  
85' muddy wtr. BHP-820#/20 min.

DST #2 2940-70 Open 1 hr.  
w/weak blow thruout. Rec. 20'  
OCM. BHP-100#/20 min.

DST #3 2988-3000 Open 40 min.  
w/weak blow for 18 min. Rec.  
35' muddy salt wtr. BHP-160#  
20 min.

DST #4 3254-72 Open 20 min.  
w/weak blow for 7 min. Rec.  
20' mud.

DST #5 3272-80 Open 30 min.  
w/weak blow for 7 min. Rec.  
15' mud BHP-940#/20 min.