

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 17 T. 12 R. 15 ^E/_W

API No. 15 — 167 — 20,819
County Number

Loc. SE NW SW

County Russell


Operator

Shields Oil Producers, Inc.

640 Acres
N

Address

Shields Building Russell, Kansas



Well No.

#9

Lease Name

Holland

Footage Location

1650 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor

Shields Drlg Co., Inc.

Geologist

M. L. Ratts

Spud Date

10-15-75

Total Depth

2610

P.B.T.D.

2569

Elev.: Gr. 1884

Date Completed

10-19-75

Oil Purchaser

Koch

DF 1887 KB 1889

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	266	Quickset	170	
Production	7 7/8	4 1/2	10 1/2	2603	Pozmix	75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		2535-2539

TUBING RECORD

Size	Setting depth	Packer set at
<u>2" EUE</u>	<u>2539</u>	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>330 BBL Water & 15,000# Sand</u>	<u>2535-2539</u>

INITIAL PRODUCTION

Date of first production <u>1-17-76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil <u>25</u> bbls.	Gas MCF	Water <u>25</u> bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) <u>Used</u>			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Shields Oil Producers, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #9	Lease Name Holland	Oil
S 17 T 12 R 15 E ^A W		

WELL LOG	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.	

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
No D.S.T.'s			Anhydrite	930
Dresser-Atlas Log			Grandhaven Lm	2428
			1st Tarkio Sd	2441
			Tarkio Lm	2508
			3rd Tarkio Sd	2532
			Elmont Lm	2560

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="text-align: center;"><i>M. Z. Rott</i> Signature</p> <p style="text-align: center;"><i>Prod. Eng.</i> Title</p> <p style="text-align: center;">1-21-76 Date</p>
---------------	---