

17-12-15W
52-52-AC

DRILLERS' WELL LOG

DATE COMMENCED: April 17, 1975
DATE COMPLETED: April 24, 1975

KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

API# 15-167-20,734

Louis M. Mai
OPE # 3
SE SE NE of Sec. 17-T12-R15
Russell County, Kansas



ELEVATION: 1820 K.B.

0 - 140'	Post Rock, Clay, Sand Streaks
140 - 520'	Sand and Shale
520 - 569'	Shale
569 - 863'	Red Bed
863 - 905'	Anhydrite
905 - 1035'	Shale
1035 - 2681'	Shale and Lime
2681 - 2911'	Lime
2911 - 2914'	Shale
2914 - 2944'	Lime and Shale
2944 - 2960'	Shale
2960 - 3213'	Lime
3213 - 3246'	Lime and Shale
3246 - 3306'	Dolomite
3306'	RTD

FORMATION TOPS

Anhydrite	863
Grand Haven	2363
Tarkio Lime	2443
3rd Sand	2470
Howard	2643
Topeka	2691
Heebner	2911
Toronto	2933
Douglas	2944
Kansas City	2960
Base K.C.	3213
Arbuckle	3246
RTD	3306

SURFACE PIPE: Set 724' of
8 5/8", 28# used pipe, w/175
sacks 60/40 Pozmix, 3% cc and
150 sacks Common 3% cc.

PRODUCTION PIPE:
Ran 4 1/2", 11.60# casing @ 3305'
w/375 sacks 50/50 Pozmix, 18%
salt, 2% Gel CPH2 & floreal.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 29th day of April 1975.

Dorothy M. Wagner
Notary Public

Commission Expires: April 11, 1978

