

17-12-15W
NE-SE-NE

DRILLERS' WELL LOG

DATE COMMENCED: April 24, 1975
DATE COMPLETED: May 1, 1975


KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

API #15-167-20,725
Louis M. Mai
OFF # 4
NE SE NE of Sec. 17-T12-R15W
Russell County, Kansas

ELEVATION: 1831 K.B.

FORMATION TOPS

Anhydrite	884
G. Haven	2387
Dover Lime	2416
Tarkio Lime	2462
3rd	2480
Elmont	2509
Howard	2655
Severy Sand	2691
Topeka	2702
Heebner	2921
Tornoto	2942
Douglas	2956
Kansas City	2972
Base K. C.	3225
Cong.	3258
RTD	3285



0 - 100'	Clay, Post Rock, Sand Streaks
100 - 190'	Sand
190 - 294'	Shale and Sand
294 - 418'	Sand
418 - 440'	Hard Sand
440 - 580'	Sand and Shale
580 - 884'	Red Bed
884 - 922'	Anhydrite
922 - 1020'	Shale
1020 - 2567'	Shale and Lime
2567 - 2921'	Lime
2921 - 2924'	Shale
2924 - 2942'	Lime and Shale
2942 - 2956'	Lime
2956 - 2972'	Shale
2972 - 3225'	Lime
3225 - 3258'	Lime and Shale
3258 - 3285'	Lime, Shale, Chert, Sand
3285'	RTD

SURFACE PIPE - Set 768' of
8 5/8", 28# used pipe w/175
sacks 60/40 Pozmix, 3% cc and
150 sacks Common, 3% cc.

PRODUCTION PIPE

Ran 4 1/2", 10.5# new casing
@ 3284 w/375 sacks 50/50 Pozmix,
2% Gel, 18% salt, CFR 2 and floreal

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 6th day of May 1975.

Norothy M. Hague
Notary Public

Commission Expires: April 11, 1978