

17-12-15W  
SE-NE-NE

DRILLER'S WELL LOG

DATE COMMENCED: May 1, 1975  
DATE COMPLETED: May 9, 1975

KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas

API # 15-167-20,736

Louis M. Mai  
OWB # 3  
SE NE NE of Sec. 17-T12-N15  
Russell County, Kansas



ELEVATION: 1845 K.S.

0 - 86'	Clay, Post Rock
86 - 458'	Sand, Shale
458 - 461'	Hard Sand
461 - 475'	Sand
475 - 478'	Hard Sand
3 - 590'	Sand and Shale
590 - 893'	Red Bed
893 - 932'	Anhydrite
932 - 1049'	Red Bed
1049 - 1198'	Shale
8 - 2493'	Shale and Lime
2493 - 2517'	Coring
2517 - 2670'	Lime and Shale
2670 - 2934'	Lime
2934 - 2937'	Shale
2937 - 2954'	Lime and Shale
2954 - 2968'	Lime
2968 - 2986'	Shale
2986 - 3238'	Lime
3238 - 3274'	Lime and Shale
3274 - 3300'	Lime, Shale, Chert and Sand
3300'	RTD

FORMATION TOPS

Anhydrite	893
Howard	2669
Severy Sand	2705
Topeka	2716
Hastner	2934
Turnsto	2954
Douglas	2968
Kansas City	2986
Base K.S.	3238
Cong.	3274
RTD	3300

SEWAGE PIPE:

Set 915' of 8 5/8", 21" new pipe w/200 sacks 60/40 Pozmix, 2 1/2 Gal, 3/4 cc and 200 sacks Cement, 3/4 cc.

PRODUCTION PIPE:

Run 4 1/2", 10.5' new casing @ 3282' w/375 sacks 50/50 Pozmix, 2 1/2 Gal, 1 1/2 salt.

AFFIDAVIT

STATE OF KANSAS }  
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 13th day of May, 1975.

Dorothy M. Hogue  
Notary Public