

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

Plotted Texas CO.

50110 d


Company - VALERIUS OIL & GAS CO.  
Farm - Oswald-Wilcox "B" No. 2.

SEC. 17 T. 12 R. 15 W  
NE NW NW

DEEPENING RECORD

Total Depth. 3282' DF PB 3205' DF  
Comm. 7-3-24 Comp. 9-24-24  
Shot or Treated.  
Contractor.  
Issued. 12-7-46

County. Russell  
KANSAS



CASING:  
15 1/2" 370' 8 1/2" 2452'  
12 1/2" 885' 6" 2629'  
10" 1520' 5" 2930'

Elevation. \_\_\_\_\_

Production. 125 B

Figures indicate Bottom of Formations.

clay blue	210	slate	1947
red rock	220	lime	1953
slate blue	245	red rock	1963
sand wh	265	lime	2000
slate blue	290	red rock	2010
lime sand	370	lime	2037
slate blue	374	slate pink	2070
sand W	390	red rock	2085
slate gy	391	lime	2105
sand lgt	403	slate	2120
slate blue	406	lime	2140
sand gy	422	slate	2150
lime gy	428	lime	2240
slate blue	450	slate	2245
lime gy	465	lime	2256
slate blue	475	slate	2320
lime gy	479	lime	2324
slate blue	485	slate	2360
slate blk	495	lime	2370
sand gy	505	slate brown	2380
lime gy	520	slate blue	2390
sand wh	528	lime	2393
slate blue	545	slate	2449
red rock	562	lime	2450
sand wh	565	slate GAS	2466
lime gy	586	sand gy	2474
red rock	860	show oil	2478
lime gy	865	slate	2483
red rock	875	lime	2485
lime	877	slate	2510
red rock	885	lime	2560
sand	888	slate blue	2580
lime	935	lime brown	2582
red rock	1040	slate blue	2595
slate	1085	slate sdy	2605
red rock	1165	slate blue	2622
slate	1195	lime gy	2630
lime	1220	slate blue	2656
salt	1230	lime gy	2665
slate	1278	shale blue	2675
salt	1493		
slate	1520	lime gy	2685
lime	1528	slate blue	2698
slate	1560	lime gy	2752
lime	1570	slate blue	2764
slate	1623	lime gy	2769
red rock	1643	slate blue	2774
slate	1650	lime gy	2798
lime	1670	oil show	2775
red rock	1685	slate blk	2803
lime	1715	lime	2840
red rock	1750	slate blk	2870
lime	1867	oil & gas show	
Gas 1800		lime	2897
red rock	1885	slate blk	2907
lime	1905	lime	2932
shale	1915	slate blk	2930
lime	1935	red rock	2940



DEEPENING RECORD

Old T.D. 3000  
Comm. - 10- 6-26  
Comp. - 10-10-26  
Prod. - Before deepen-  
ing 40 BPD  
after deepening  
160 BPD

lime sdy 3000-3050  
Total Depth

DEEPENING RECORD

Sohio Petro. Co.  
Comm. - 9-22-43  
Comp. - 10- 6-43  
Prod. - 21E B in  
48 hrs.

Acidized w/4000G.

5 1/2" csg @ 2950  
Perf - 3155-58  
Perf - 3160-65

lime & shale? 3180 DF  
Total Depth

DEEPENING RECORD

Sohio Petro. Co.  
Comm. 1-16-46  
Comp. 2-8-46  
Pmp 29 BO w/1BW  
in 24 hrs.

Had been producing  
from the entire  
LKC zone thru a  
perf. loose liner  
set below the 220'  
zone. Producing  
16 BO & 123 BWPD.  
Pld loose liner,  
set & cem. 311' of 4 1/2"  
liner @ 3213 w/300sx

conglomerate 3235DF  
granite wash 3256DF  
Total Depth 3282DF  
PB 3205DF