


E.M.

20" 8 1-4
15 1-2 6 5-8
12 1-2 5 3-16

LOCATION SE cSW NW
FARM Oswald-Wilcox NO.16 COUNTY Russell
COMPANY Valerius Oil and Gas Co.
CONTRACTOR Stearns and Streeter.
COMMENCED Feb 6, 1926 COMPLETED April 8, 1926



TOTAL DEPTH SHOT QUARTS BETWEEN
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Valerius O&Gas Co.

Tulsa, Okla.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 1st 24 hr

72bbls.

REMARKS

Formation	Depth	Formation	Depth.
brown shale 20" at 8'	25	brown shale s oft	2075
dark shale	65	lime white hard	2100.
grey shale	125	grey shale soft	2120
blue shale	135	red rock soft	2155
brown shale	165	lime white hard	2200 1 1/2 BWP HR
blue shale	210	blue shale	2210
white shale	240	lime white hard	2235
blue shale	250	white shale soft	2256
red rock	287	lime white hard	2270
grey shale	295	blue shale soft	2287
sand white	310	1BW per hr lime white hd	2310
HPW 295-310		blue shle light	2345
white shale	320	blue shale soft	2390
red rock	338	lime white hard	2385
browns and	408	blue shale soft	2410
lime white hard	410	lime whie hard	2415
sand	452	blue shald soft	2427
blue shale 15 1/2 at 452	485	lime whie hard	2440
sand white	510	blue shale soft	2446
blue shale	520	white slate soft	2468
sand	526	dark shale	2518
blue shale	590	lime white hd	2525
U.R. 15 1/2 at 546		8 1/4 2503 dark shale soft	2532
red rock	595	shellu soft	2545
blue shale	600	oil at 2532-45	
red rock	605	dark shale soft	2560
brown sand	625	lime wh hard	2568
red rock	932	dark shale	2575
chalk white	935	blue shale soft	2625
white lime	971	lime white hard	2630
red rock	1090	wh slate soft	2680
light grey shale	1130	blue shale soft	2697
red rock	1215	2BW 2685 lime wh hd	2714
grey shale	1270	grey shale	2733
salt	1540	gray shale soft	2785
blue shale soft	1555	lime wh hd	2875
lime white hard	1561	grey shale soft	2880
10" casing 1556		lime wh hd	2902
blue shale	1595	blue shale soft	2925
blue shale soft	1660	lime wh hard	2958
white lime hard	1670	grey lime hd	2968
grey shale soft	1680	blue shale soft	2975
red rock	1700	lime wh dodge	2987
red rock soft	1705	lime wh hd	2993
blue shale soft	1712	blue shale soft	2999
lime white hard	1723	pink shale soft	3004
brown shale soft	1750	red shale soft SLM	3006
lime white hard	1775	blue shale soft 3001	3009
red rock soft	1815	lime oil SLM 3009 top	3015
blue shale soft	1850	pay 3009	
lime white hard	1862	oil sand	3019
blue shale	1894	the oil sand from 3015-3019-	
lime white hard	1920	is the first oil sand noted in	
red rock soft	1940	this field.	
lime white hard	1963		
brown shale soft	1978		
lime white hard	1995		
red rock soft	2010		
lime white hard	2029		
blue shale soft	2040		
lime white hard	2053		
brown shale soft	2062		
lime white hard	2070		