


10" 1648 FARM Oswald-Wilcox NO. 18 COUNTY Russell
 20" 19 8 1-4 2612 COMPANY Valerius-Wilcox Oil Co.
 15 1-2 639 6 5-8 3153 CONTRACTOR Stearns & Stroeter.
 12 1-2 1136 5 3-16 COMMENCED March 31, 1926. COMPLETED May 23, 1926.
 TOTAL DEPTH SHOT QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 10/30/26.

ELEVATION

INITIAL PRODUCTION 120 bbls.

1st 24 hrs. 240 bbls 2nd

24 hrs.

Formation	Depth	Formation	Depth	Formation	Depth
yellow sand	30	red rock	1790	lime hrd	2870
(20" at 19')		lime	1868	lime	2900
blue sand	130	slate	1875	sand	2910
blue shale	140	lime	1900	(enough water to drill)	
blue shale	172	red rock	1918	(With show oil at 2900')	
gray slate	205	lime	1995	lime	2930
red rock	245	shale	2010	slate	2953
gray slate	265	blue shale	2030	white lime	2965
red bed	270	lime	2050	lime	2968
gray slate (HFW 280')	280	broken lime	2055	green shale	2972
gray sand	290	slate	2080	lime shell	2974
gray slate	295	lime	2105	brown shale	2984
brown slate	320	red rock	2140	blue shale	2989
sand	395	lime	2155	lime-hil pay	2997
(More water 320')		slate	2170	(Set 6 5/8" at 2989')	
iron	397	lime	2180		
sand	433	slate	2190	Bottom hole	2997'
blue mud	460	brown shale	2200		
(Set 15 1/2" at 436')		lime	2207	Top of pay and bottom	
sand	490	blue shale	2225	hole are both steel	
blue mud	498	lime	2255	line measurements.	
blue mud	510	blue slate	2287		
blue shale	540	lime	2295		
sand	548	gray slate	2308		
gray slate	558	lime	2320		
(U/R & lowered pipe 551')		blue shale	2345		
iron	560	lime	2365		
slate	565	slate	2380		
gray slate	576	brown slate	2390		
sand (Water 576')	598	lime	2400		
red rock	900	blue shale	2475		
?	908	lime	2490		
lime	948	shale	2495		
(Set 12 1/2" at 910')		lime	2505		
red rock	1063	(show oil 2505')			
blue shale hrd	1090	broken sand	2520		
blue shale	1100	lime	2542		
gray shale	1112	gray slate	2545		
red rock	1140	shale	2550		
brown shale	1180	(8 1/2" at 2547')			
blue shale	1200	lime	2555		
gray slate	1250	white lime	2560		
salt	1510	light shale	2578		
slate	1518	sandy slate	2587		
lime (10" at 1520')	1523	brown lime	2600		
lime	1541	shale	2606		
slate	1555	lime	2611		
lime	1605	shale	2665		
gray slate	1630	gray slate	2674		
white lime	1654	lime	2683		
brown slate	1675	blue slate	2695		
gray slate	1695	lime	2715		
lime	1705	blue shale	2720		
pink slate	1715	lime	2835		
lime	1750	lime hrd	2870		