

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted Texas CO.
Sec. 19 T. 12 R. 15W.

Location. NE corner.

DEEPENING RECORD.

Casing Record.

County. Russell

OCT 22 1932



10" 1529 Farm. I.J.Ginther No. 1
 20" 9 8" 2480 Company. Wilcox O. & Gas Co.
 15 1/2" 425 65/8" 2993 Contr. Stearns & Streeter.
 12 3/4" 918 53/16" Comm. 12-19-26 Comp. 3-18-27
 Total Depth 3036 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 10-22-32

60 bbls T.D. 3021.

Formation	Depth	Formation	Depth	New Prod. - Swab 3 BPHR. TD. 3036.	Depth.
mudd yellow	20	slate blue	1890	lime hard	3015
slate blue	80	lime grey	1915	lime soft	3019
slate grey	130	shale grey	1920	lime hard	3021
slate blue	135	shale pink	1930	oil at 3015-3019	
shale blue	195	lime	1980	lowered 65/8 to 2991.	
shale grey sdy	210	slate grey	1995	TD.	
slate grey	230	slate red	2015	SIM 3021. Top pay 2994	
slate brown	253	lime	2110		
shale brown	260	slate grey	2115	DEEPENING RECORD.	
sand	270	red rock	2135		
slate grey	295	slate grey	2145	Old Total Depth 3021.	
shale brown	310	lime	2165		
shale pink	325	shale pink	2175	Comm. 3-25-32 Comp. 4- 6-32.	
sand	350	slate grey	2215		
shale blue	360	slate blue	2255	Prod. Swab 3 B. Per hr.	
slate blue	365	slate	2285		
sand grey	425	lime	2330	lime white 3021-3022	
slate grey	430	shale blue	2340	shale blue 3024	
slate blue	435	slate blue	2360	lime hard white 3030	
shale blue	440	slate grey	2405	lime soft dark 3034	
slate blue	447	lime shells	2412	lime wh med hard 3036	
sand grey	470	slate grey	2435	TD.	
shale blue	475	shale blue	2440	in the dark soft lime from 3030	
slate blue	532	lime gas	2450	to 3034 additional oil was	
sand blue	545	shale blue	2460	encountered. which swabbed	
slate blue	555	slate blk	2480	three bbls per hr.	
iron	570	lime	2495		
shale red	575	slate blue	2500		
slate	595	slate grey	2525		
red rock	905	lime	2530		
conglomerate	914	slate blue	2535		
lime	918	lime dark	2542		
lime white	955	slate blue	2550		
red rock	1050	lime	2565		
slate brown	1070	shale blue	2580		
slate blue	1090	lime	2590		
slate grey	1125	slate grey	2605		
slate brown	1220	slate blue	2645		
slate blue	1258	2 BW 2635-2640			
salt	1325	slate grey	2665		
slate blue	1529	slate blue	2670		
lime	1542	lime	2675		
slate blue	1550	slate blue	2685		
lime	1560	shale	2690		
broken lime	1575	lime	2703		
lime	1600	slate blue	2720		
slate	1610	lime	2740		
broken lime	1625	slate	2750		
slate grey	1632	lime	2805		
lime	1640	shale	2810		
slate grey	1648	slate grey	2815		
lime	1670	lime white	2835		
slate brown	1685	lime	2910		
shale red	1695	slate grey	2918		
slate blue	1705	lime white	2956		
lime	1730	slate blue	2960		
shale brown	1745	lime	2974		
slate blue	1750	slate blue	2980		
lime grey	1768	slate brown	2986		
slate blue	1775	lime	2988		
slate brown	1805	shale blue	2992		
shale brown	1815	sand lime	2995		
lime white	1865	showing oil and wtr.			
lime	1875				