

CENTRAL PETRO. CORP.
Rusch No. 3-A.

SEC. 19 T. 12 R. 15W
SW SE SW

Plotted Texas CO.

County. Russell

Total Depth. 3080'
Comm. 1-28-37 Comp. 2-26-37
Shot or Treated.
Contractor. Harry Gore
Issued. 3-20-37

MAR 20 1937



CASING:

15 1/8" 395'
12 1/2" 615'
10 " 955' Left in.
8 1/4" 2480 UR 2754
6 5/8" 2940 Left in.
5 3/16" 90 run @ 3020'

Elevation.

Production, Pot. 646 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	2020	lime	2875
clay yellow	35	red rock	2030	shale blue	2880
slate blue	200	lime	2035	lime	2912
shale sdy	230	shale blue	2045	shale blue	2915
sand water	240	lime	2055	lime	2930
slate blue	270	shale light	2065	lime brown	2973
slate light	315	lime	2075	show oil 2950	
red rock	340	shale red	2085	shale black	2975
s and water	355	lime	2100	lime	2982
mud yellow	365	shale	2105	shale blue	2990
shale blue	375	lime	2125	lime(Dodge)	3008
shale light	390	red rock	2135	slate	3023
shale blue	420	lime	2145	lime(Oswald)	3048
shale sdy	440	slate blue	2150	shale	3050
sand water	475	lime	2190	lime	3055
iron	480	shale	2198	shale	3058
shale blue	492	lime	2215	lime brown	3080
sand	510	shale blue	2230	Total Depth.	
slate blue	520	lime	2245		
iron & slate	530	shale red	2265		
sand	550	lime	2310		
slate drk	565	shale blue	2330	SAND RECORD	
sand & iron	580	lime	2335		
sand	600	shale blue	2340	Top Dodge 2990-3008	
slate blue	610	lime	2355	18' pay	
red rock	935	shale blue	2370	Top Oswald 3023-3048	
shale blue	940	lime	2400	25' Pay 3060-3068	
lime anhydrite	980	shale & shells	2460		
red rock	1105	lime	2465	WATER RECORD	
slate blue	1120	shale	2470		
slate & shells blue	1145	lime	2475	2 BW 220	
red rock	1225	gas sand	2480	10 BW 230-240	
shale blue	1280	lime	2490	HFW 350	
salt white	1575	slate	2519	HFW 450	
shale blue	1580	lime	2525	8 BWP 660	
lime	1592	shale blue	2560	8 BWP 780-795	
shale & shells	1600	lime	2590	1 BW 2230	
shale light	1625	shale blue	2595	7 BW 2665-2670	
lime	1635	lime	2600		
lime shells & slate	1670	shale blue	2605		
lime	1690	lime	2622		
red rock	1715	shale light	2631		
lime shells	1720	lime	2645		
lime	1740	shale blue	2670		
lime brkn	1790	shale sdy	2680		
red rock	1820	shale drk	2690		
lime	1840	shale blue	2698		
shale blue	1850	lime	2700		
lime white(show or	1900	shale blue	2706		
shale blue gas	1905	lime	2710		
lime 1870-80)	1930	slate blue	2720		
red rock	1940	lime	2740		
lime	1965	shale blue	2757		
red rock	1975	lime	2840		
lime	1995	show oil 2757-60			
slate blue	2010	shale blue	2845		

SOHIO PETROLEUM CO.
#3 Rusch "A"
19-12-15W

DEEPENING RECORD:

Comm. 2-4-48 Comp. 2-14-48

Production Est. 23 BO / 23 BWPD

DD 3160

Total Depth

Tops

Anhydrite 940

Ft. Riley 1820

Topeka 2757

Lansing-Kansas 3048

City

WELL LOG SHEET - KANSAS GEOLOGICAL SURVEY

WELL LOG SHEET - KANSAS GEOLOGICAL SURVEY