

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **SOHIO PETROLEUM**


SEC. 19 T. 12 N. 15W
 LOC. N½ NE SE
 450' EL & 205' NL S½

FARM **South Fairport** NO. **S-1**
Water Supply System

TOTAL DEPTH **735'**
 COMM. **3-2-67** COMP. **3-5-67**
 SHOT OR TREATED
 CONTRACTOR **Rosencrantz-Bemis Drlg.**
 ISSUED **4-27-68**

COUNTY **Rush**

KANSAS



CASING

20 10
 15 **X 7" 735'**
 12 6
 13 5

ELEVATION **None**

PRODUCTION **WTR Supply Well**
Dak 410-25

FIGURES INDICATE BOTTOM OF FORMATIONS

0	30	Clay
30	120	Shale
120	190	Shale
190	210	Sand
210	225	Sand
225	270	Shale & sand streaks
270	405	Fire clay
405	465	Sand
465	475	Hard sand & pyrite ✓
475	570	Pyrite, shale ✓
570	590	Sand
590	675	Red bed, pyrite ✓
675	715	Red bed

TOPS: SMP
 Dakota 405
 Base Dakota 480
 TD 735

Drilled 9" hole, run 712.42 ft. of Owner's used 7" casing, completed and developed well.

ROSENCRANTZ-BEMIS DRILLING CO.
Box 713
Great Bend, Kansas

[Signature]
O. E. Rosencrantz