


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Oswald. "A" No. 1

SEC. 2 T. 12 R. 16W
SW SW SW

Total Depth. 3506'
Comm. 4-27-59 Comp. 5-6-59
Shot or Treated.
Contractor.
Issued. 4-2-60

County Ellis
KANSAS



CASING:
8 5/8" 208' cem. w/150 sx.
4 1/2" 3505.5' cem. w/125 sx.

Elevation. 1846 DF

Production. 166 BOPD

Figures indicate Bottom of Formations.

shale & shells	392
sand & shale	515
sand	660
red bed	1009
anhydrite	1046
shale & shells	1600
shale & lime	2480
shale & shells	2750
lime	2960
lime & shale	3095
lime	3305
lime & shale	3350
shale	3383
lime	3506
Total Depth	

TOPS:	
Anhydrite	1009
Heebner	3016
Toronto	3034
Lansing	3061
Simpson Sand	3379
Arbuckle	3387

DST #1 3071-3122' Op. 1 hr. Rec.
15' SOCM 125" MSW-BHP 605#

DST #2 3329-3390 Op. 1 hr. Rec.
105' SOCM BHP 875#

DST #3 3390-95. Op 30 min. Rec.
610' clean oil, BHP 1040#

DST #4 3396-3408 Op. 30 min. Rec.
2040" oil, no wtr. BHP 1020#

DST #5 3409-18 Op 30 min. Rec.
1500' wtr., BHP 1020#

DRILLING-IN
MIST & CO. Perf. w/24 shots from
3396-3400. Oil Fill up 2800" in
2 hrs., no wtr., test 10 BOPH,
Put on Pump