


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.  
Farm- Oswald "B" No. 1

SEC. 2 T. 12 R. 16W  
SE SE NW

Total Depth. 3449'  
Comm. 6-7-59 Comp. 6-16-59  
Shot or Treated.  
Contractor. Birmingham-Bartlett  
Issued. 9-12-59

County Ellis  
KANSAS



Elevation. 1807' DF

Production. 91 BOPD

CASING:

8 5/8" 198' cem w/150 sx.  
5 1/2" 3430' cem w/200 sx.

Figures Indicate Bottom of Formations.

clay & rock	110
shale	197
shale & shells	490
sand & shale	600
shale & red bed	940
red bed	967
Anhydrite	1002
shale & shells	1700
shale & lime	2757
lime	2935
lime & shale	3025
lime	3369
lime & shale	3395
lime	3449 RTD
Total Depth	

TOPS:

Anhydrite	968
Topeka	2708
Heebner	2976
Toronto	3000
Lansing	3027
Simpson	3357
Arbuckle	3377

DST #1 2750-70', op 45 min., fair flow.  
rec. 300' muddy wtr., specks oil.  
BHP 720#.

DST #2 3010-44', op 25 mins., rec. 8'  
mud. BHP 0#.

DST #3 3044-62', op 30 min., rec. 7'  
mud. BHP 0#.

DST #4 3116-71', op 1 hr., rec. 130'  
O&G cut mud. BHP 360#.

DST #5 3175-92', op 1 hr., rec. 125'  
sl. oil cut muddy wtr. BHP 300#.

DST #6 3217-43', op 1 hr., rec. 150' very  
heavy oil cut mud. BHP 820#.

DST #7 3261-3310', op 25 min., weak blow  
11 mins., rec. 30' mud. BHP 700#.

DST #8 3346-69', op 35 min., weak blow  
20 min. Rec. 30' mud. BHP 700#.